

CALL NO. 414

CONTRACT ID. 153225

WEBSTER COUNTY

FED/STATE PROJECT NUMBER 117GR15R065-CB06

DESCRIPTION KY 283 (KY 283)

WORK TYPE ASPHALT SURFACE WITH BRIDGE

PRIMARY COMPLETION DATE 6/30/2016

LETTING DATE: September 25,2015

Sealed Bids will be received electronically through the Bid Express bidding service until 10:00 AM EASTERN DAYLIGHT TIME September 25,2015. Bids will be publicly announced at 10:00 AM EASTERN DAYLIGHT TIME.

NO PLANS ASSOCIATED WITH THIS PROJECT.

REQUIRED BID PROPOSAL GUARANTY: Not less than 5% of the total bid.

TABLE OF CONTENTS

PART I SCOPE OF WORK

- PROJECT(S), COMPLETION DATE(S), & LIQUIDATED DAMAGES
- CONTRACT NOTES
- STATE CONTRACT NOTES
- ASPHALT MIXTURE
- DGA BASE
- INCIDENTAL SURFACING
- COMPACTION OPTION B
- SPECIAL NOTE(S) APPLICABLE TO PROJECT
- LIQUIDATED DAMAGES
- WASTE AND BORROW SITES
- COORDINATION OF WORK WITH OTHER CONTRACTS
- EDGE KEY
- GUARDRAIL
- ASPHALT MILLING AND TEXTURING
- BASE FAILURE REPAIR
- TYPICAL SECTION DIMENSIONS
- TRAFFIC CONTROL PLAN
- EROSION CONTROL PLAN FOR MAINTENANCE PROJECTS
- SKETCH MAP(S)
- MATERIAL SUMMARY
- SUMMARY SHEET(S)
- TYPICAL SECTION(S)
- DETAIL SHEET(S)
- BRIDGE DETAIL FOR PAVING PROJECT

PART II SPECIFICATIONS AND STANDARD DRAWINGS

- SPECIFICATIONS REFERENCE
- SUPPLEMENTAL SPECIFICATION
- STANDARD DRAWINGS THAT APPLY ENTIRE LIST 2012
- DELINEATORS FOR GUARDRAIL
- GUARDRAIL COMPONENTS
- STEEL BEAM GUARDRAIL ("W" BEAM)
- GUARDRAIL POSTS
- LANE CLOSURE TWO-LANE HIGHWAY

PART III EMPLOYMENT, WAGE AND RECORD REQUIREMENTS

- LABOR AND WAGE REQUIREMENTS
- EXECUTIVE BRANCH CODE OF ETHICS
- KENTUCKY EQUAL EMPLOYMENT OPPORTUNITY ACT OF 1978 LOCALITY 1,2,3,4 / STATE (OVER 250,000)
- PROJECT WAGE RATES LOCALITY 1 / FEDERAL & STATE

PART IV INSURANCE

PART V BID ITEMS

PART I SCOPE OF WORK

ADMINISTRATIVE DISTRICT - 02

CONTRACT ID - 153225

117GR15R065-CB06

COUNTY - WEBSTER

PCN - 0211702831501 CB06 117 0283 001-006

KY 283 (KY 283) (MP 1.840) FROM 0.443 MILE NORTH OF BECKLEY OSBORNE ROAD EXTENDING NORTH TO SMITH WEST ROAD (MP 5.029), A DISTANCE OF 03.19 MILES.ASPHALT RESURFACING GEOGRAPHIC COORDINATES LATITUDE 37:35:41.58 LONGITUDE 87:36:43.79

PCN - 0211702831502 CB06 117 0283 B00005N

KY 283 (KY 283) (MP 3.494) FROM 0.737 MILE NORTH OF COTTINGHAM PRATT ROAD SOUTH EXTENDING NORTH TO 0.602 MILE SOUTH OF SHADY GROVE KNOBLICK ROAD OVER MELTON DITCH. (MP 3.500), A DISTANCE OF 0.01 MILES.BRIDGE

GEOGRAPHIC COORDINATES LATITUDE 37:35:41.82 LONGITUDE 87:36:43.67

COMPLETION DATE(S):

COMPLETED BY 06/30/2016 APPLIES TO ENTIRE CONTRACT

CONTRACT NOTES

PROPOSAL ADDENDA

All addenda to this proposal must be applied when calculating bid and certified in the bid packet submitted to the Kentucky Department of Highways. Failure to use the correct and most recent addenda may result in the bid being rejected.

BID SUBMITTAL

Bidder must use the Department's Expedite Bidding Program available on the Internet web site of the Department of Highways, Division of Construction Procurement. (www.transportation.ky.gov/construction-procurement)

The Bidder must download the bid file located on the Bid Express website (www.bidx.com) to prepare a bid packet for submission to the Department. The bidder must submit electronically using Bid Express.

JOINT VENTURE BIDDING

Joint venture bidding is permissible. All companies in the joint venture must be prequalified in one of the work types in the Qualifications for Bidders for the project. The bidders must get a vendor ID for the joint venture from the Division of Construction Procurement and register the joint venture as a bidder on the project. Also, the joint venture must obtain a digital ID from Bid Express to submit a bid. A joint bid bond of 5% may be submitted for both companies or each company may submit a separate bond of 5%.

UNDERGROUND FACILITY DAMAGE PROTECTION

The contractor is advised that the Underground Facility Damage Protection Act of 1994, became law January 1, 1995. It is the contractor's responsibility to determine the impact of the act regarding this project, and take all steps necessary to be in compliance with the provision of the act.

SPECIAL NOTE FOR COMPOSITE OFFSET BLOCKS

Contrary to the Standard Drawings (2012 edition) the Cabinet will allow 6" composite offset blocks in lieu of wooden offset blocks, except as specified on proprietary end treatments and crash cushions. The composite blocks shall be selected from the Cabinet's List of Approved Materials.

<u>REGISTRATION WITH THE SECRETARY OF STATE BY A FOREIGN</u> <u>ENTITY</u>

Pursuant to KRS 176.085(1)(b), an agency, department, office, or political subdivision of the Commonwealth of Kentucky shall not award a state contract to a person that is a foreign entity required by KRS 14A.9-010 to obtain a certificate of authority to transact business in the Commonwealth ("certificate") from the Secretary of State under KRS 14A.9-030 unless the person produces the certificate within fourteen (14) days of the bid or proposal opening. If the foreign entity is not required to obtain a certificate as provided in KRS 14A.9-010, the foreign entity should identify the applicable exception. Foreign entity is defined within KRS 14A.1-070.

For all foreign entities required to obtain a certificate of authority to transact business in the Commonwealth, if a copy of the certificate is not received by the contracting agency within the time frame identified above, the foreign entity's solicitation response shall be deemed non-responsive or the awarded contract shall be cancelled.

Businesses can register with the Secretary of State at https://secure.kentucky.gov/sos/ftbr/welcome.aspx.

SPECIAL NOTE FOR PROJECT QUESTIONS DURING ADVERTISEMENT

Questions about projects during the advertisement should be submitted in writing to the Division of Construction Procurement. This may be done by fax (502) 564-7299 or email to kytc.projectquestions@ky.gov. The Department will attempt to answer all submitted questions. The Department reserves the right not to answer if the question is not pertinent or does not aid in clarifying the project intent.

The deadline for posting answers will be 3:00 pm Eastern Daylight Time, the day preceding the Letting. Questions may be submitted until this deadline with the understanding that the later a question is submitted, the less likely an answer will be able to be provided.

The questions and answers will be posted for each Letting under the heading "Questions & Answers" on the Construction Procurement website (www.transportation.ky.gov/contract). The answers provided shall be considered part of this Special Note and, in case of a discrepancy, will govern over all other bidding documents.

HARDWOOD REMOVAL RESTRICTIONS

The US Department of Agriculture has imposed a quarantine in Kentucky and several surrounding states, to prevent the spread of an invasive insect, the emerald ash borer.

Hardwood cut in conjunction with the project may not be removed from the state. Chipping or burning on site is the preferred method of disposal.

INSTRUCTIONS FOR EXCESS MATERIAL SITES AND BORROW SITES

Identification of excess material sites and borrow sites shall be the responsibility of the Contractor. The Contractor shall be responsible for compliance with all applicable state and federal laws and may wish to consult with the US Fish and Wildlife Service to seek protection under Section 10 of the Endangered Species Act for these activities.

ACCESS TO RECORDS

The contractor, as defined in KRS 45A.030 (9) agrees that the contracting agency, the Finance and Administration Cabinet, the Auditor of Public Accounts, and the Legislative Research Commission, or their duly authorized representatives, shall have access to any books, documents, papers, records, or other evidence, which are directly pertinent to this contract for the purpose of financial audit or program review. Records and other prequalification information confidentially disclosed as part of the bid process shall not be deemed as directly pertinent to the contract and shall be exempt from disclosure as provided in KRS 61.878(1)(c). The contractor also recognizes that any books, documents, papers, records, or other evidence, received during a financial audit or program review shall be subject to the Kentucky Open Records Act, KRS 61.870 to 61.884.

In the event of a dispute between the contractor and the contracting agency, Attorney General, or the Auditor of Public Accounts over documents that are eligible for production and review, the Finance and Administration Cabinet shall review the dispute and issue a determination, in accordance with Secretary's Order 11-004. (See attachment)

10/29/12



Steven L. Beshear Governor Lori H. Flanery Secretary

Room 383, Capitol Annex 702 Capital Avenue Frankfort, KY 40601-3462 (502) 564-4240 Fax (502) 564-6785

SECRETARY'S ORDER 11-004

FINANCE AND ADMINISTRATION CABINET

Vendor Document Disclosure

WHEREAS, in order to promote accountability and transparency in governmental operations, the Finance and Administration Cabinet believes that a mechanism should be created which would provide for review and assistance to an Executive Branch agency if said agency cannot obtain access to documents that it deems necessary to conduct a review of the records of a private vendor that holds a contract to provide goods and/or services to the Commonwealth; and

WHEREAS, in order to promote accountability and transparency in governmental operations, the Finance and Administration Cabinet believes that a mechanism should be created which would provide for review and assistance to an Executive Branch agency if said agency cannot obtain access to documents that it deems necessary during the course of an audit, investigation or any other inquiry by an Executive Branch agency that involves the review of documents; and

WHEREAS, KRS 42.014 and KRS 12.270 authorizes the Secretary of the Finance and Administration Cabinet to establish the internal organization and assignment of functions which are not established by statute relating to the Finance and Administration Cabinet; further, KRS Chapter 45A.050 and 45A.230 authorizes the Secretary of the Finance and Administration Cabinet to procure, manage and control all supplies and services that are procured by the Commonwealth and to intervene in controversies among vendors and state agencies; and

NOW, THEREFORE, pursuant to the authority vested in me by KRS 42.014, KRS 12.270, KRS 45A.050, and 45A.230, I, Lori H. Flanery, Secretary of the Finance and Administration Cabinet, do hereby order and direct the following:

- I. Upon the request of an Executive Branch agency, the Finance and Administration Cabinet ("FAC") shall formally review any dispute arising where the agency has requested documents from a private vendor that holds a state contract and the vendor has refused access to said documents under a claim that said documents are not directly pertinent or relevant to the agency's inquiry upon which the document request was predicated.
- II. Upon the request of an Executive Branch agency, the FAC shall formally review any situation where the agency has requested documents that the agency deems necessary to



- conduct audits, investigations or any other formal inquiry where a dispute has arisen as to what documents are necessary to conclude the inquiry.
- III. Upon receipt of a request by a state agency pursuant to Sections I & II, the FAC shall consider the request from the Executive Branch agency and the position of the vendor or party opposing the disclosure of the documents, applying any and all relevant law to the facts and circumstances of the matter in controversy. After FAC's review is complete, FAC shall issue a Determination which sets out FAC's position as to what documents and/or records, if any, should be disclosed to the requesting agency. The Determination shall be issued within 30 days of receipt of the request from the agency. This time period may be extended for good cause.
- IV. If the Determination concludes that documents are being wrongfully withheld by the private vendor or other party opposing the disclosure from the state agency, the private vendor shall immediately comply with the FAC's Determination. Should the private vendor or other party refuse to comply with FAC's Determination, then the FAC, in concert with the requesting agency, shall effectuate any and all options that it possesses to obtain the documents in question, including, but not limited to, jointly initiating an action in the appropriate court for relief.
- V. Any provisions of any prior Order that conflicts with the provisions of this Order shall be deemed null and void.

SPECIAL NOTE FOR RECIPROCAL PREFERENCE

Reciprocal preference to be given by public agencies to resident bidders

By reference, KRS 45A.490 to 45A.494 are incorporated herein and in compliance regarding the bidders residency. Bidders who want to claim resident bidder status should complete the Affidavit for Claiming Resident Bidder Status along with their bid in the Expedite Bidding Program. Submittal of the Affidavit should be done along with the bid in Bid Express.

Contract ID: 153225 Page 11 of 97

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

DGA BASE

Unless otherwise noted, the Department estimates the rate of application for DGA Base to be 115 lbs/sy per inch of depth.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

SPECIAL NOTES FOR PRECAST CONCRETE CULVERT REPLACEMENT

I. DESCRIPTION

Perform all work in accordance with the Department's 2012 Standard and Supplemental Specifications, applicable Special Provisions and Special Notes, and Standard and Sepia Drawings, except as hereafter specified. Article references are to the Standard Specifications. This work shall consist of:

- (1) Site preparation; (2) Clearing and grubbing and removal of all obstructions;
- (3) Removal of existing structure; (4) Drilling and blasting, if required, and common and solid rock excavation; (5) Constructing precast concrete culvert; (6) Constructing embankment, roadway, pavement, and shoulders; (7) Restoration, final dressing, cleanup, and seeding; (8) Maintain and control traffic; and (9) Any other work as specified by this contract.

I. MATERIALS AND DESIGN

All materials shall be sampled and tested in accordance with the Department's Sampling Manual. Make the materials available for sampling a sufficient time in advance of the use of the materials to allow for the necessary time for testing unless otherwise specified in these Notes.

- **A. Precast Concrete Culvert.** Provide a **28' X 28' X 10'-3 1/8"** Precast Concrete Culvert, headwalls or end walls, corner panels, wing walls, and toe walls, meeting the requirements of the included design drawings. Design for fill cover height of 1'-0" minimum and 2'-0" maximum and clear roadway width of 28 feet with 0° skew as shown on the drawings. Prior to fabrication, furnish the Engineer shop drawings approved by a "Registered Professional Engineer" licensed in Kentucky. Prior to acceptance, the Department reserves the right to sample and test the concrete, and accessories at any time. Materials not conforming to contract requirements are subject to rejection, whether in place or not.
- **B. Foundation Preparation and Bedding.** Removal of the existing culvert will be considered incidental to Precast Concrete Arch Culvert.

- **C. Culvert Backfill.** Use only Flowable Fill for the backfilling of the proposed structure.
- **D. Guardrail.** (2) Detached precast parapet headwalls 2'-0" tall by 15" thick with inserts for guardrail attachment. See also Special Notes for Guardrail
- **E. Pavement and Shoulders.** Use Dense Graded Base, Class 2 Asphalt Base 1.00D PG64-22, and Class 2 Asphalt Surface 0.38D PG64-22.
- **F. Seeding and Protection.** Use Seed Mixture No. III.
- **G. Erosion Control.** See Special Notes for Erosion Control Plan.
- H. Maintain and Control Traffic. See Traffic Control Plan.

III. CONSTRUCTION METHODS

- A. Maintain and Control Traffic. See Traffic Control Plan.
- **B. Site Preparation.** Be responsible for all site preparation, including, but not limited to; clearing and grubbing; tree removal, common and solid rock excavation, backfilling and embankment in place; saw cutting; removal of existing culvert, obstructions, or any other items; disposal of materials, waste, and debris; temporary and permanent erosion control; restoration, final dressing, cleanup, and seeding and protection. Perform all site preparation only as approved or directed by the Engineer.
- **C. Excavation and Removal of Existing Structures.** Sawcut pavement to a neat edge and remove the existing culvert. Be responsible for all common and solid rock excavation, pavement removal, and removal of existing structure. Removal of existing culvert will be considered incidental to Precast Concrete Arch Culvert. Provide positive drainage of slopes and ditches at all times during and upon completion of construction. Waste all removed materials at sites off the right of way obtained by the Contractor at no additional cost to the Department. Perform all excavation and removal of existing structure only as approved or directed by the Engineer.
- **D. Structure Excavation.** Be responsible for all excavation required for foundation preparation, culvert, head walls or end walls, wing walls, toe walls, and all other excavation required by the work. Excavate rock in channel as required to allow for installation of bedding and culvert with the designed fill cover height. Provide positive drainage of slopes and ditches at all times during and upon completion of construction. Waste all excavation at sites off the right of way obtained by the Contractor at no additional cost to the Department. Perform all structure excavation only as approved or directed by the Engineer.

- **E. Foundation Preparation and Bedding.** Perform foundation preparation as outlined in the detail drawings.
- **F. Precast Concrete Arch Culvert.** Construct the arch culvert in accordance with the detail drawings. Provide for the arch culvert manufacturer to furnish an expert field engineer on site during all phases of the fabrication, construction, backfilling, and guardrail installation over culvert for consulting purposes. Be responsible for field layout and survey of the proposed culvert. Obtain the Engineer's approval of the final centerline, flow line and skew prior to backfilling. Provide positive drainage upon completion of the project.
- **G. Head walls, End Walls, Wing Walls, Toe Walls.** Construct head walls, end walls, wing walls, and toe walls according to the arch culvert manufacturer's approved design or as approved by the Engineer. Four precast wingwalls with mounting hardware 12'-7" tall by 12'-0" long.
- **H. Backfill and Embankment.** Construct flowable backfill and embankments as directed by the Engineer. Warp finished slopes to match existing undisturbed slopes as directed by the Engineer. Provide positive drainage of slopes and ditches at all times during and upon completion of construction.
- **I.** Clean and Re-establish the Existing Shoulders and Ditches. Grade and restore the shoulders and ditches in the project limits to match the existing adjacent features to be left in place or as directed by the Engineer. Provide positive drainage of slopes and ditches at all times during and upon completion of construction.
- **J. Pavement & Shoulder Restoration.** Restore pavement and shoulders over the culvert trench and widen approaches as shown on the typical or as directed by the Engineer and transition to match the adjacent undisturbed typical section. Provide positive drainage of pavement and shoulders at all times during and upon completion of construction. After constructing culvert, backfill, and embankment, construct crushed stone base and place asphalt base and reopen the road to traffic. After opening to traffic, correct settlement with additional Leveling and Wedging, as applicable, until the Engineer determines the culvert backfill and base are sufficiently stabilized to allow placement of asphalt surface. Once stabilized, construct final asphalt surface courses. Restore pavement and shoulders outside the culvert trench and base widening areas.
- **M. Final Dressing, Clean Up, and Seeding and Protection.** After all work is completed, completely remove debris from the construction site. Perform Class A Final Dressing on all disturbed areas, both on and off the Right of-Way. Sow all disturbed earthen areas with Seed Mixture No. III.
- **N. Restoration.** Be responsible for all damage to public and/or private property resulting from the work. Restore all damaged features in like kind materials and design.

- **O. On-Site Inspection.** Make a thorough inspection of the site prior to submitting a bid and be thoroughly familiar with existing conditions so that the work can be expeditiously performed after a contract is awarded. The Department will consider submission of a bid as evidence of this inspection having been made and will not honor any claims resulting from site conditions.
- **P. Caution.** Do not take information shown on the plans and in this proposal and the types and quantities of work listed as an accurate or complete evaluation of the material and conditions to be encountered during construction. Without regard to the materials encountered, all roadway excavation shall be unclassified. It shall be distinctly understood that any reference to rock, earth, or any other material on the plans or cross sections, whether in numbers or words, letters, or lines, is solely for the Department's information and is not to be taken as an indication of classified excavation or the quantity of either rock, earth, or any other material involved. The bidder must draw his own conclusion as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and no claim will be considered for additional compensation if the conditions encountered are not in accordance with the information shown.
- **Q. Right-of-Way Limits.** The department has not determined exact limits of Right-of-Way. Limit work activities to obvious Right-of-Way, permanent or temporary Easements, and work areas secured by the Department through consent and release of the adjacent property owners. Be responsible for all encroachments onto private lands.
- **R.** Utility Clearance. Work around and do not disturb existing utilities. It is not anticipated that any utility facilities will require relocation and/or adjustment; however, in the event utilities are discovered, the utility companies will work concurrently with the Contractor while relocating their facilities. If the total delay exceeds ten working days, an extension of the specified completion date will be negotiated with the Contractor for delay to the Contractor's work.

IV. METHOD OF MEASUREMENT

Only the bid items listed will be measured for payment. All other items required to complete the work shall be incidental to the listed items.

- A. Maintain and Control Traffic. See Traffic Control Plan.
- **B. Site Preparation.** Site Preparation will be measured as one lump sum.
- **C. Erosion Control Plan.** See Special Notes for Erosion Control Plan.
- **D. Clearing and Grubbing, Excavation and Embankment.** Contrary to Sections 202, 204, 205 and 206 Clearing and Grubbing, Roadway Excavation, Structure Excavation,

Borrow Excavation, Embankment in Place, and granular backfill will not be measured for separate payment, but shall be incidental to Site Preparation.

- **E. Backfill Material.** Backfill materials will not be measured for payment but shall be incidental to the culvert.
- **F. Precast Concrete Arch Culvert.** See Special detail drawings; however, foundation preparation, culvert design, manufacturer's technical representative, head walls, end walls, wing walls, corner panels and toe walls will not be measured for separate payment, but shall be incidental to the arch culvert.
- **G. Restoration, Final Dressing, Clean Up, and Seeding and Protection.** Restoration, final dressing, clean up, and seeding and protection will not be measured for payment, but shall be incidental to Site Preparation and erosion Control plan as applicable.

V. Basis of Payment

No direct payment will be made other than for the bid items listed. All other items required to complete the construction shall be incidental to the bid items listed.

- **A. Maintain and Control Traffic.** See Traffic Control Plan.
- **B. Precast Concrete Arch Culvert.** Payment at the contract unit price per linear foot shall be full compensation for all materials, equipment, labor and incidentals necessary to complete the work as specified in these notes and the Standard Specifications for culvert design and manufacturer's representative; foundation preparation, precast concrete arch culvert, headwalls, end walls, corner panels, wing walls, and toe walls.
- **C. Site Preparation.** Payment at the contract lump sum unit price shall be full compensation for all materials, equipment, labor, and incidentals, including, but not limited to; bridge removal; clearing and grubbing; common and solid rock excavation, backfilling and embankment in place; removal of obstructions, or any other items; disposal of materials; cleaning inlet and outlet ditches; restoration, final dressing, and cleanup.
- **D. Erosion Control Plan.** See Special Notes for Erosion Control Plan.

SPECIAL NOTES FOR COMPLETION DATE & LIQUIDATED DAMAGES

Time is of the essence. The overall completion date for the contract is June 30, 2016; however, remove the existing culvert and install and backfill the new culvert, restore the pavement and reopen KY 283 to through traffic no later than May 31, 2016. Contrary to the Liquidated Damages specified in Section 108.09, Liquidated Damages in the amount of \$2,000.00 per calendar day will be assessed for each calendar day or part of a day KY 283 remains closed to through traffic after the 15 days maximum road closure.

Contrary to section 108.09, Liquidated damages will be assessed for the months of December through March.

Contrary to Section 108.09, Liquidated Damages will be assessed regardless of whether seasonal limitations prohibit the Contractor from performing work on the controlling operation.

All liquidated damages will be applied accumulatively.

All other applicable portions of Section 108 apply.

SPECIAL PROVISION FOR WASTE AND BORROW SITES

Obtain U.S. Army Corps of Engineer's approval before utilizing a waste or borrow site that involves "Waters of the United States". The Corps of Engineers defines "Waters of the United States" as perennial or intermittent streams, ponds or wetlands. The Corps of Engineers also considers ephemeral streams, typically dry except during rainfall but having a defined drainage channel, to be jurisdictional waters. Direct questions concerning any potential impacts to "Waters of the United States" to the attention of the appropriate District Office for the Corps of Engineers for a determination prior to disturbance. Be responsible for any fees associated with obtaining approval for waste and borrow sites from the U.S. Army Corps of Engineer or other appropriate regulatory agencies.

1-296 Waste & Borrow Sites 01/02/2012

COORDINATION OF WORK WITH OTHER CONTRACTS


Be advised, there may be an active project adjacent to or within this project. The Engineer will coordinate the work of the Contractors. See Section 105.06.

Bridge replacement must be completed before paving operations may begin.

SPECIAL NOTE FOR EDGE KEY

Construct Edge Keys at the beginning of project, end of project, at railroad crossings, and at ramps, as applicable. Unless specified in the Contract or directed by the Engineer, do not construct edge keys at intersecting streets, roads, alleys, or entrances. Cut out the existing asphalt surface to the required depth and width shown on the drawing and heel the new surface into the existing surface. The Department will make payment for this work at the Contract unit price per ton for Asphalt Pavement Milling and Texturing, which shall be full compensation for all labor, materials, equipment, and incidentals for removal and disposal of the existing asphalt surface required to construct the edge key.

EDGE KEY



Thickness = $\underline{1}$ Inch

L = 100 LF

L= Length of Edge Key

1-3309 Edge key by Ton 01/02//2012

SPECIAL NOTES FOR GUARDRAIL

I. DESCRIPTION

Except as specified herein, perform all work in accordance with the Department's Standard and Supplemental Specifications and Standard and Sepia Drawings, current editions. Article references are to the Standard Specifications.

Furnish all equipment, labor, materials, and incidentals for the following work items:

(1) Site preparation; (2) Remove existing guardrail systems; (3) Construct Guardrail, End Treatments, Bridge End Connectors, and Terminal Sections, as applicable; (4) Delineators for guardrail; (5) Maintain and control traffic; and (6) all other work specified as part of this contract.

II. MATERIALS

Except as specified herein, provide for all materials to be sampled and tested in accordance with the Department's Sampling Manual and make the materials available for sampling a sufficient time in advance of the use of the materials to allow for the necessary time for testing.

- A Maintain and Control Traffic. See Traffic Control Plan.
- **B. Guardrail.** Furnish guardrail system components according to section 814 and the Standard Drawings; except use steel posts only, no alternates.
- **C. Delineators for Guardrail.** Furnish white and/or yellow Delineators for Guardrail according to the Delineators for Guardrail Sepia Drawing.
- **D. Erosion Control.** See Special Notes for Erosion Control.

III. CONSTRUCTION METHODS

- A. Maintain and Control Traffic. See Traffic Control Plan.
- **B. Site Preparation.** Remove existing guardrail system including the guardrail end treatments, Bridge End connectors and all other elements of the existing guardrail system as per Section 719, except that the Contractor will take possession of all concrete posts and all concrete associated with existing bridge and/or guardrail end treatments. Locate all disposal areas off the Right of Way. Be responsible for all site preparation, including but not limited to, clearing and grubbing, excavation, embankment, and removal of all obstructions or any other items; regrading, reshaping, adding and compacting of suitable materials on the existing shoulders to provide proper template or foundation for the

Guardrail Page 2 of 4

guardrail; filling voids left as the result of removing existing guardrail and guard posts with dry sand; temporary pollution and erosion control; disposal, of excess and waste materials and debris; and final dressing, cleanup, and seeding and protection. Perform all site preparation as approved or directed by the engineer.

C. Guardrail. Except as specified herein, construct guardrail system according to Section 719 and the Standard Drawings. Locations listed on the summary and/or shown on the drawings are approximate only. The Engineer will determine the exact termini for individual guardrail installations at the time of construction. Unless directed otherwise by the Engineer, provide a minimum two (2) foot shoulder width. Construct radii at entrances and road intersections as directed by the Engineer.

Erect guardrail to the lines and grades shown on current Standard Drawings or as directed by the Engineer by any method approved by the Engineer which allows construction of the guardrail to the true grade without apparent sags.

When removing existing guardrail and installing new guardrail, do not leave the blunt end exposed where it would be hazardous to the public. Contrary to Section 719 of the Standard Specifications the Contractor will retain possession of the existing guardrail. When it is not practical to complete the construction of the guardrail and the permanent end treatments and terminal sections first, provide a temporary end by connecting at least 25 feet of rail to the last post, and by slightly flaring, and burying the end of the rail completely into the existing shoulder. If left overnight, place a drum with bridge panel in advance of the guardrail end and maintain during use.

- **D. Delineators for Guardrail.** Construct Delineators for Guardrail according to the Delineators for Guardrail Sepia Drawing.
- **E. Property Damage.** Be responsible for all damage to public and/or private property resulting from the work. Restore damaged roadway features and private property at no additional cost to the Department.
- **F. Coordination with Utility Companies.** Locate all underground, above ground and overhead utilities prior to beginning construction. Be responsible for contacting and maintaining liaison with all utility companies that have utilities located within the project limits. Do not disturb existing overhead or underground utilities. It is not anticipated that any utility facilities will need to be relocated and/or adjusted; however, in the event that it is discovered that the work does require that utilities be relocated and/or adjusted, the utility companies will work concurrently with the Contractor while relocating their facilities. Be responsible for repairing all utility damage that occurs as a result of guardrail operations at no additional cost to the Department.
- **G. Right of Way Limits**. The Department has not established exact limits of the Right-of-Way. Limit work activities to obvious Right-of-Way, permanent or temporary easements, and work areas secured by the Department through consent and release of the adjacent

Contract ID: 153225 Page 23 of 97

Guardrail Page 3 of 4

property owners. Be responsible for all encroachments onto private lands.

Guardrail Page 4 of 4

- **H. Disposal of Waste.** Dispose of all removed concrete, debris, and other waste and debris off the Right-of-Way at sites obtained by the Contractor at no additional cost to the Department. See Special; Note for Waste and Borrow.
- **I. Final Dressing, Clean Up, and Seeding and Protection.** Apply Class A Final Dressing to all disturbed areas, both on and off the Right-of-Way. Sow all disturbed earthen areas according to the Special Notes for Erosion Control.
- **J. Erosion Control.** See Special Notes for Erosion Control.

IV. METHOD OF MEASUREMENT

- **A. Maintain and Control Traffic.** See Traffic Control Plan.
- **B. Site preparation.** Other than the bid items listed, the Department will not measure Site Preparation for separate payment but shall be incidental to Guardrail, End Treatments, Bridge End Connectors, and Terminal Sections as applicable.
- C. Guardrail. See Section 719.04.
- **D. Delineators for Guardrail.** See Delineators for Guardrail Sepia Drawing.
- **E. Erosion Control.** See Special Notes for Erosion Control.

V. BASIS OF PAYMENT

- A. Maintain and Control Traffic. See Traffic Control Plan.
- B. Guardrail. See Section 719.05.
- **C. Delineators for Guardrail.** See Delineators for Guardrail Sepia Drawing.
- **D. Erosion Control.** See Special Notes for Erosion Control.

1-3414 Remove Replace Guardrail 01/02/2012

SPECIAL NOTE FOR ASPHALT MILLING AND TEXTURING

Begin paving operations within <u>48 hours</u> of commencement of the milling operation. Continue paving operations continuously until completed. If paving operations are not begun within this time period, the Department will assess liquidated damages at the rate prescribed by Section 108.09 until such time as paving operations are begun.

Take possession of the millings and recycle the millings or dispose of the millings off the Right-of-Way at sites obtained by the Contractor at no additional cost to the Department.

1-3520 48 hours Contractor keeps millings 01/2/2012

SPECIAL NOTE FOR BASE FAILURE REPAIR CB06-117-0283-001-006

Repair locations listed on the summary are approximate only. The Engineer will determine actual repair locations and dimensions at the time of construction. Prior to overall milling and/or leveling and wedging, excavate the designated base failure areas by milling to a depth 8-10 inches below the existing asphalt pavement surface level. Dispose of the excavated materials at waste sites off the Right-of-Way obtained by the Contractor at no additional cost to the Department. See Special Note for Waste and Borrow.

Backfill the excavated areas with Class 2 Asphalt Base 1.00D PG64-22. Compact the asphalt base to the compaction required in Section 403.03.10. Seal the asphalt base with leveling and wedging. Perform all base failure repairs in such a manner that removal and replacement are completed on the same day. Do this work as one of the Contractor's first operations in order to allow further compaction by traffic. Do not mill or place new asphalt surface over repaired base failure areas until a minimum of 7 calendar days have elapsed after placement of the asphalt base. After a minimum of 7 calendar days and when the Engineer determines the base failure repair areas have sufficiently stabilized, begin milling and/or resurfacing operations. Prior to milling and/or constructing the new asphalt surface, level and wedge any settlement of the repair areas.

The bidder must draw conclusions as to the conditions encountered. The Department does not give any guarantee as to the accuracy of the data and will not consider any claim for additional compensation if the materials encountered that are not in accord with the classification shown.

Accept payment at the Contract unit prices per square yard for Base Failure repair and per ton for Leveling and Wedging as full compensation for all labor, materials, equipment, and incidentals for removing payment and disposing of the materials, furnishing and placing asphalt base, leveling and wedging, and all other items necessary to complete the work according to these notes to the satisfaction of the Engineer.

1-3606basefailurerepairmillinlaypaybysy 01/02/2012

Contract ID: 153225 Page 27 of 97

SPECIAL NOTE FOR TYPICAL SECTION DIMENSIONS

Consider the dimensions shown on the typical sections for pavement and shoulder widths and thickness' to be nominal or typical dimensions. The Engineer may direct or approve varying the actual dimensions to be constructed to fit existing conditions. Do not widen existing pavement or shoulders unless specified elsewhere in this proposal or directed by the engineer.

1-3725 Typical Section Dimensions 01/02/2012

TRAFFIC CONTROL PLAN

TRAFFIC CONTROL GENERAL

Except as provided herein, maintain and control traffic in accordance with the 2012 Standard and Supplemental Specifications, and the Standard and Sepia Drawings. Article references are to the Standard Specifications. Except for the roadway and traffic control bid items listed, all items of work necessary to maintain and control traffic will be paid at the lump sum bid price to "Maintain and Control Traffic".

Contrary to Section 106.01, traffic control devices used on this project may be new, or used in like new condition, at the beginning of the work and maintained in like new condition until completion of the work.

PROJECT PHASING & CONSTRUCTION PROCEDURES

At the discretion of the Engineer, days and hours may be specified when road and lane closures will not be allowed.

KY 283 may be closed to through traffic at MP 3.497 for removal of the existing structural and installation of the precast concrete arch culvert subject to the following conditions:

- 1. Provide a proposed closure schedule to the Engineer fourteen (14) days prior to beginning work. Obtain the Engineer's approval prior to beginning work.
- 2. The Department will provide public notification, variable message boards, the detour route, and detour signs. The Contractor is responsible for road closure, work zone signs, barricades, and physically barricading the site. Notify the Engineer immediately of any anticipated or proposed deviations from the approved work schedule
- 3. The closure will be allowed for a maximum of 15 calendar days. All safety and traffic control devices must be in place before the reopening of KY 283. Paving operations shall begin once the road is reopened to the general public.
- 4. The Contractor will not be required to provide continuous access to single family, duplex, or triplex residential properties or farms during working hours; however, the Contractor shall provide reasonable egress and ingress to each such property when actual operations are not in progress at that location. The time during which a residential entrance is blocked shall be the minimum length of time required for actual operations, shall not be extended for the Contractor's convenience, and in no case shall exceed six (6) hours. The Contractor shall notify all residents twenty-four hours in advance of any driveway or entrance closings and shall make any accommodations necessary to meet the access needs of disabled residents.

5. Maintain local traffic and provide access to side streets and roads, schools, churches, commercial properties and apartments or apartment complexes of four or more units at all times. Maintain alternating one way traffic during working hours at all other times during construction outside of the 15 day closure. The clear lane width shall be <u>9</u> feet. If traffic should be stopped due to construction operations, and a school bus on an official run arrives on the scene, make provisions for the passage of the bus as quickly as possible.

LANE & SHOULDER CLOSURES

Except for the allowable days specified in the phasing for road closure to place and backfill the culvert, do not leave lane closures in place during non-working hours. Shoulder closures may be maintained during non-working hours; however do not park vehicles or store materials on a closed shoulder during non-working hours.

SIGNS

Contrary to section 112.04.02, only long term signs (signs intended to be continuously in place for more than 3 days) will be measured for payment; short term signs (signs intended to be left in place for 3 days or less) will not be measured for payment but shall be incidental to Maintain and Control Traffic. Individual signs will be measured only once for payment, regardless of how many times they are set, reset, removed, and relocated during the duration of the project. Replacements for damaged signs directed by the Engineer to be replaced due to poor condition or reflectivity will not be measured for payment.

PORTABLE CHANGEABLE MESSAGE SIGNS

If deemed necessary by the Engineer, Portable Changeable Message Signs will be installed, operated, and maintained by the Department.

BARRICADES

Barricades used in lieu of barrels and cones for channelization or delineation shall be incidental to Maintain and Control Traffic according to Section 112.04.01. Barricades used to protect pavement removal areas and for road closures will be bid as each according to Section 112.04.04. Individual barricades will be measured only once for payment, regardless of how many times they are set, reset, removed, and relocated during the duration of the project. Replacements for damaged barricades directed by the Engineer to be replaced due to poor condition or reflectivity will not be measured for payment.

TRAFFIC COORDINATOR

Designate an employee to be traffic coordinator. The designated Traffic Coordinator must be certified by the American Traffic Safety Services Association (ATSAA). The Traffic Coordinator shall provide for inspection of the project maintenance of traffic once every

two hours during the Contractor's operations and at any time a lane closure is in place. The Traffic Coordinator shall report all incidents throughout the work zone to the Engineer on the project. The Contractor shall furnish the name and telephone number where the Traffic Coordinator can be contacted at all times. During any period when a lane closure is in place, the Traffic Coordinator will arrange for personnel to be present on the project at all times to inspect the traffic control, and maintain the signing and barricades. The personnel will have access on the project to a radio or telephone to be used in case of emergencies or accidents.

PAVEMENT EDGE DROP-OFFS

Do not allow a pavement edge between opposing directions of traffic or lanes that traffic is expected to cross in a lane change situation with an elevation difference greater than $1\frac{1}{2}$ ". Place warning signs in advance of and at 1500 feet intervals throughout the drop-off area. Provide dual posting on both sides of the traveled way. Wedge transverse transitions between resurfaced and unresurfaced areas which traffic may cross with asphalt mixture for Leveling and Wedging. Remove the wedges prior to placement of the final surface course.

Protect pavement edges that traffic is not expected to cross, except accidentally, as follows:

Less than 2" - No protection required.

2" to 4" - Place plastic drums, vertical panels, or barricades every 50 feet. Cones may be used in place of plastic drums, panels, and barricades during daylight working hours. Wedge with DGA or asphalt mixture for Leveling and Wedging with a 1:1 or flatter slope in daylight hours, or 3:1 or flatter slope during nighttime hours, when work is not active in the drop-off area.

SPECIAL NOTE FOR EROSION CONTROL

I. DESCRIPTION

Perform all erosion and water pollution control work in accordance with the Department's Standard Specifications current edition, these notes, and interim Supplemental Specifications, Special Provisions and Special Notes, and Standard and Sepia Drawings, current editions, and as directed by the Engineer. Section references are to the Standard Specifications. This work shall consist of:

(1) Developing and preparing a Best Management Practices Plan (BMP) tailored to suit the specific construction phasing for each site within the project; (2) Preparing the project site for construction, including locating, furnishing, installing, and maintaining temporary and/or permanent erosion and water pollution control measures as required by the BMP prior to beginning any earth disturbing activity on the project site; (3) Clearing and grubbing and removal of all obstructions as required for construction; (4) Removing all erosion control devices when no longer needed; (5) Restoring all disturbed areas as nearly as possible to their original condition; (6) Preparing seedbeds and permanently seeding all disturbed areas; (7) Providing a Kentucky Erosion Prevention and Sediment Control Program (KEPSC) qualified inspector; and (8) Performing any other work to prevent erosion and/or water pollution as specified by this contract, required by the BMP, or as directed by the Engineer.

II. MATERIALS

Furnish materials in accordance with these notes, the Standard Specifications and interim Supplemental Specifications, and applicable Special Provisions and Special Notes, and Standard and Sepia Drawings, current editions. Provide for all materials to be sampled and tested in accordance with the Department's Sampling Manual. Unless directed otherwise by the Engineer, make the materials available for sampling a sufficient time in advance of the use of the materials to allow for the necessary time for testing.

III. CONSTRUCTION

Be advised, these Erosion Control Plan Notes do not constitute a BMP plan for the project. Jointly with the Engineer, prepare a site specific BMP plan for each drainage area within the project in accordance with Section 213 and the supplemental specifications. Provide a unique BMP at each project site using good engineering practices taking into account existing site conditions, the type of work to be performed, and the construction phasing, methods and techniques to be utilized to complete the work. Be responsible for all erosion prevention, sediment control, and water pollution prevention measures required by the BMP for each site. Represent and warrant compliance with the Clean Water Act (33 USC Section 1251 et seq.), the 404 Permit, the 401 Water Quality

Contract ID: 153225 Page 32 of 97

Erosion Control Page 2 of 4

Certification, and applicable state and local government agency laws, regulations, rules, specifications, and permits. Contrary to Section 105.05, in case of discrepancy between theses notes, the Standard Specifications, interim Supplemental Specifications, Special and Special Notes, Standard and Sepia Drawings, and such state and local government agency requirements, adhere to the most restrictive requirement.

Conduct operations in such a manner as to minimize the amount of disturbed ground during each phase of the construction and limit the haul roads to the minimum required to perform the work.. Preserve existing vegetation not required to be removed by the work or the contract. Seed and/or mulch disturbed areas at the earliest opportunity. Use silt fence, silt traps, temporary ditches, brush barriers, erosion control blankets, sodding, channel lining, and other erosion control measures in a timely manner as required by the BMP and as directed or approved by the Engineer. Prevent sediment laden water from leaving the project, entering an existing drainage structure, or entering a steam.

Provide for erosion control measures to be in place and functioning prior to any earth disturbance within a drainage area. Compute the volume and size of silt control devices necessary to control sediment during each phase of construction. Remove sediment from silt traps before they become a maximum of ½ full. Maintain silt fence by removing accumulated trappings and/or replacing the geotextile fabric when it becomes clogged, damaged, or deteriorated, or when directed by the Engineer. Properly dispose of all materials trapped by erosion control devices at approved sites off the right of way obtained by the Contractor at no additional cost to the Department (See Special Note for Waste and Borrow).

As work progresses, add or remove erosion control measures as required by the BMP applicable to the Contractor's project phasing and construction methods and techniques. Update the volume calculations and modify the BMP as necessary throughout the duration of the project. Ensure that an updated BMP is kept on site and available for public inspection throughout the life of the project.

After all construction is complete, restore all disturbed areas in accordance with Section 212. completely remove all temporary erosion control devices not required as part of the permanent erosion control from the construction site. Prior to removal, obtain the Engineer's concurrence of items to be removed. Grade the remaining exposed earth (both on and off the Right of-Way) as nearly as possible to its original condition, or as directed by the Engineer. Prepare the seed bed areas and sow all exposed earthen areas with the applicable seed mixture(s) according to Section 212.03.03.

Erosion Control Page 3 of 4

IV. MEASUREMENT

Erosion Control Blanket. If required by the BMP, the Department will measure Erosion Control Blanket according to Section 212.04.07.

Sodding. If required by the BMP, the Department will measure Sodding according to Section 212.04.08.

Channel Lining. If required by the BMP, the Department will measure Channel Lining according to Sections 703.04.04-703.04.07.

Erosion Control. Contrary to Sections 212.04 and 213.04, other than Erosion Control Blankets, Sodding, and Channel Lining, the Department will measure Erosion Control as one lump sum. The Department will not measure developing, updating, and maintaining a BMP plan for each site; providing a KEPSC qualified inspector; locating, furnishing, installing, inspecting, maintaining, and removing erosion and water pollution control items; Roadway Excavation, Borrow Excavation, Embankment In Place, Topsoil Furnished and Placed, and Spreading Stockpiled Topsoil; Topdressing Fertilizer, Temporary and Permanent Seeding and Protection, Special Seeding Crown Vetch, and Temporary Mulch; Sedimentation Basin and Clean Sedimentation Basin, Silt Trap Type "A" and Clean Silt Trap Type "A"; Silt Trap Type "B" and Clean Silt Trap Type "B"; Silt Trap Type "C" and Clean Silt Trap Type "C"; Temporary Silt Fence and Clean Temporary Silt Fence; Plants, Vines, Shrubs, and Trees; Gabion and Dumped Stone Deflectors and Riffle Structures; Boulders; and Temporary Ditches and clean Temporary Ditches; and all other erosion and water pollution control items required by the BMP or the Engineer, but shall be incidental to Erosion Control.

V. Basis of Payment

Erosion Control Blanket. If not listed as a bid item, but required by the BMP, the Department will pay for Erosion Control Blankets as Extra Work according to Sections 104.03 and 109.04.

Sodding. If not listed as a bid item, but required by the BMP, the Department will pay for Sodding as Extra Work according to Sections 104.03 and 109.04.

Channel Lining. If not listed as a bid item, but required by the BMP, the Department will pay for Channel Lining as Extra Work according to Sections 104.03 and 109.04.

Erosion Control Page 4 of 4

> **Erosion Control.** Contrary to Sections 212.05 and 213.05, other than Erosion Control Blanket, Sodding, and Channel Lining, payment at the Contract lump sum price for Erosion Control, shall be full compensation for all materials, equipment, labor and incidentals necessary to complete the erosion and water pollution control work as specified in these notes, Sections 212 and 213, the Supplemental Specifications, applicable Special Provisions and Special Notes, and Standard and Sepia Drawings, including but not limited to developing, updating, and maintaining a BMP plan for each site; providing a KEPSC qualified inspector; locating, furnishing, installing, inspecting, maintaining, and removing erosion and water pollution control items; Roadway Excavation, Borrow Excavation, Embankment In Place, Topsoil Furnished and Placed, and Spreading Stockpiled Topsoil; Topdressing Fertilizer, Temporary and Permanent Seeding and Protection, Special Seeding Crown Vetch, and Temporary Mulch; Sedimentation Basin and Clean Sedimentation Basin, Silt Trap Type "A" and Clean Silt Trap Type "A"; Silt Trap Type "B" and Clean Silt Trap Type "B"; Silt Trap Type "C" and Clean Silt Trap Type "C"; Temporary Silt Fence and Clean Temporary Silt Fence; Plants, Vines, Shrubs, and Trees; Gabion and Dumped Stone Deflectors and Riffle Structures; Boulders; and Temporary Ditches and clean Temporary Ditches; and all other erosion and water pollution control items required by the BMP or the Engineer

MATERIAL SUMMARY

CONTRACT ID: 153225	117GR15R065-CB06	0211702831501
CONTRACT ID: 153225	117GR15R065-CB06	0211702831501

KY 283 (KY 283) FROM 0.443 MILE NORTH OF BECKLEY OSBORNE ROAD EXTENDING NORTH TO SMITH WEST ROAD ASPHALT SURFACE WITH BRIDGE, A DISTANCE OF 3.19 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	220.00	TON
0010	00190	LEVELING & WEDGING PG64-22	146.00	TON
0015	00301	CL2 ASPH SURF 0.38D PG64-22	2,135.00	TON
0020	02562	TEMPORARY SIGNS	250.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (PAVING)	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - (PAVING)	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING	125.00	TON
0040	03240	BASE FAILURE REPAIR	92.00	SQYD
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	26,000.00	LF
0050	06514	PAVE STRIPING-PERM PAINT-4 IN	34,000.00	LF
0055	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 153225 117GR15R065-CB06 0211702831502


KY 283 (KY 283) FROM 0.737 MILE NORTH OF COTTINGHAM PRATT ROAD SOUTH EXTENDING NORTH TO 0.602 MILE SOUTH OF SHADY GROVE KNOBLICK ROAD OVER MELTON DITCH. ASPHALT SURFACE WITH BRIDGE, A DISTANCE OF .01 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00212	CL2 ASPH BASE 1.00D PG64-22	40.00	TON
0010	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	5.00	EACH
0015	02014	BARRICADE-TYPE III	2.00	EACH
0020	02351	GUARDRAIL-STEEL W BEAM-S FACE	87.50	LF
0025	02355	GUARDRAIL-STEEL W BEAM-S FACE A	100.00	LF
0030	02360	GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH
0035	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0040	02381	REMOVE GUARDRAIL	100.00	LF
0045	02562	TEMPORARY SIGNS	150.00	SQFT
0050	02650	MAINTAIN & CONTROL TRAFFIC - (BRIDGE)	1.00	LS
0055	24381EC	G/R STEEL W BEAM-S FACE (NESTED)	62.50	LF
0060	02569	DEMOBILIZATION	1.00	LS
0065	00001	DGA BASE	40.00	TON
0070	02483	CHANNEL LINING CLASS II	50.00	TON
0075	20257NC	SITE PREPARATION - (BRIDGE)	1.00	LS
0080	21415ND	EROSION CONTROL - (BRIDGE)	1.00	LS
0085	23060EN	PRECAST CONCRETE ARCH CULVERT	28.00	LF


REMOVE GUARDRAIL	ET REMARKS																	
LIN FEET		20.0		50.0	20.0	50.0	50.0	50.0	50.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0
CNI	MILEPOINT MILEPOINT LIN FEET	3.516		3.516	3.516	3.516 Total	3.516 Total	3.516 Total	3.516 Total	3.516 Total								
	MILEPOINT	3.478		3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478	3.478
	LANE			SB	S S	SB	SB SB	SS S	SB	SB	SS SB	SB SB	SB SB	SS S	SB SB	as a second seco	SS	SS
	REMARKS	28' Dbl rail across bridge for a total of 56' across bridge. 50' of rail for Type 1 E.T and 25' of Radius rail for field	Entrance	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances	Entrance 28' Dbl rail across bridge for a total of 56' across bridge. 2 x 25' of Radius rail for field Entrance = 50' of rail for entrances
	LIN FEET	137.5		112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5	112.5
:	END TREAT.			Terminal Sec. No. 1	Terminal Sec. No.	Terminal Sec. No. 1 Total	Terminal Sec. No. 1 Total	Terminal Sec. No. 1	Terminal Sec. No.	Terminal Sec. No. 1 Total	Sec. No. 1	Sec. No.	Sec. No.	Sec. No.	Sec. No. 1	Sec. No. Total	Sec. No. 1	Sec. No.
2	MILEPOINT			3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505	3.505
100	BEGIN			3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490	3.490
END				Terminal Sec. No. 1	Terminal Sec. No.	Sec. No.	Terminal Sec. No.	Terminal Sec. No.	Sec. No.	Terminal Sec. No.	Terminal Sec. No.	Terminal Sec. No.	Terminal Sec. No.					
	LANE	NB		SB	SB	SB	SS S	SS	SS SS	SS S	BS B	SS S	88	as a second of the second of t	BS B	88	BS BS	88

WEBSTER COUNTY

CB06-117-0283-001-006 TYPICAL SECTION M.P 1.840 - 5.029





*DGA used to protect any drop-offs - Directed by Engineer *Where Existing Site Conditions Permit Striping as directed by the Engineer




*Where Existing Site Conditions Permit See summary for locations. Striping as directed by the Engineer


TS1BASEFAILURE







INLET END ELEVATION



NOTES

General Notes:

- THIS BRIDGE HAS BEEN DESIGNED FOR GENERAL SITE CONDITIONS. THE PROJECT ENGINEER
 SHALL BE RESPONSIBLE FOR THE STRUCTURE'S SUITABILITY TO THE EXISTING SITE CONDITIONS
 AND FOR THE HYDRAULIC EVALUATION INCLUDING SCOUR AND CONFORMATION OF SOIL
 CONDITIONS.
- 2. PRIOR TO CONSTRUCTION, CONTRACTOR MUST VERIFY ALL ELEVATIONS SHOWN THROUGH THE ENGINEER.
- 3. ALTERNATE STRUCTURES MAY BE CONSIDERED, PROVIDED THAT DRAWINGS AND CALCULATIONS SIGNED AND SEALED BY A PROFESSIONAL ENGINEER, REGISTERED IN THE STATE OF KENTUCKY, EMPLOYED BY THE PRECAST CONCRETE BRIDGE SUPPPLIER, ARE SUBMITTED TO THE ENGINEER 2 WEEKS PRIOR TO THE BID DATE FOR REVIEW AND APPROVAL.
- 4. ALTERNATE STRUCTURES MAY BE CONSIDERED, PROVIDED THAT THE ALTERNATE DESIGN DOES NOT REDUCE THE HYDRAULIC OPENING OF THE STRUCTURE AS SHOWN ON THE DRAWINGS. AT A MINIMUM THE ALTERNATE STRUCTURE MUST PROVIDE THE SAME OR LARGER SPAN AND RISE AS THE STRUCTURE SHOWN ON THE DRAWINGS.
- 5. THE PRECASE ARCH SUPPLIER MUST ATTEND THE PRE-BID MEETING, IF ONE IS HELD.
- 6. SUPPLIER OR PROPOSED ALTERNATES MUST SUBMIT AT LEAST TWO (2) INDEPENDENTLY VERIFIED FULL SCALE LOAD TESTS THAT CONFIRM THE PROPOSED DESIGN METHODOLOGY OF THE THREE SIDED/ARCH STRUCTURES(S). THE PROPOSED ALTERNATE, UPON SATISFACTORY CONFIRMATION OF DESIGN METHODOLOGY, MAY BE CONSIDERED AN ACCEPTABLE ALTERNATE.
- 7. PROPOSED ALTERNATE STRUCTURES MAY BE CONSIDERED, PROVIDED THAT THE PRECAST CONCRETE BRIDGE STRUCTURES ARE PROVIDED BY A SUPPLIER THAT HAS A MINIMUM OF TWO (2) REGISTERED PROFESSIONAL ENGINEERS ON STAFF THAT ARE DEDICATED TO THE DESIGN OF THESE TYPES OF STRUCTURES. SUPPLIER MUST PROVIDE THESE NAMES, P.E. LICENSE NUMBERS AND DATES OF HIRE AT TIME OF ALTERNATE SUBMITTAL.
- 8. THE FOUNDATION FOR THE BRIDGE IS INCIDENTAL TO THE COST OF THE BRIDGE AND WILL BE PAID USING THE BID ITEM "PRECAST CONCRETE ARCH CULVERT" BY LF.

DESIGN DATA

DESIGN LOADING:

BRIDGE UNITS: KYHL-93

HEADWALLS: EARTH PRESSURE + LIVE LOAD IMPACT WINGWALLS: EARTH PRESSURE + LIVE LOAD SURCHARGE

DESIGN FILL HEIGHT: 1'-0" MIN. TO 2'-0" MAX. FROM TOP OF CROWN TO TOP OF PAVEMENT.

DESIGN METHOD: LOAD RESISTANCE FACTOR DESIGN PER AASHTO LRFD SPECIFICATION

ASSUMED NOMINAL BEARING RESISTANCE: 5,400 PSF ASSUMED FACTORED BEARING RESISTANCE: 5,400 PSF


*AT THE TIME OF DESIGN, A GEOTECHNICAL REPORT FOR THE PROJECT SITE WAS NOT AVAILABLE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT THE ACTUAL SITE CONDITIONS AT THE TIME OF CONSTRUCTION ARE CONSISTENT WITH THE ASSUMED ALLOWABLE SOIL BEARING PRESSURE WITH A GEOTECHNICAL INVESTIGATION FROM A QUALIFIED GEOTECHNICAL ENGINEER.

MATERIALS

CONCRETE FOR FOOTINGS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI. REINFORCING STELL FOR FOOTINGS SHALL CONFORM TO ASTM A615 OR A996-GRADE 60.

- 28 LF OF 28'-0" SPAN X 10'-3 1/8" RISE PRECAST CONCRETE UNITS
- UNCOATED REINFORCEMENT (BLACK STEEL)
- TWO (2) DETACHED PRECAST PARAPET HEADWALLS 2'-0" TALL X 15" THICK WITH INSERTS FOR GUARDRAIL ATTACHMENT
- FOUR (4) PRECAST WINGWALLS WITH MOUNTING HARDWARE 12'-7" TALL X 12'-0" LONG
- JOINT SEALANT MATERIAL
- MASONITE SHIMS
- FILTER FABRIC AND PERFORATED DRAIN TILE

BRIDGE DETAIL FOR PAVING PROJECT



W = bridge width curb to curb

T = thickness of existing asphalt overlay

L = length of bridge

 $L_1 \& L_2 = length of approach pavement to be removed$

 T_R = thickness to be removed and replaced on bridge

 P_R = thickness to be removed and replaced on pavement

Note: L₁ & L₂ lengths shall be determined by using a transition rate of 100 ft/in of thickness

KY	Bridge No.	MP	W (ft)	T (in)	L_1 (ft)	L_2 (ft)	T_R	L (ft)	P_{R} (in)
Rout							(in)		
e									
283	B00008N	3.090	19.00		100.00	100.00		22	1.00
283	B00007N	3.206	19.00		100.00	100.00		42	1.00
283	B00003N	4.921	19.00		100.00	100.00		32.2	1.00

01/01/2009

PART II

SPECIFICATIONS AND STANDARD DRAWINGS

SPECIFICATIONS REFERENCE

Any reference in the plans or proposal to previous editions of the *Standard Specifications* for Road and Bridge Construction and Standard Drawings are superseded by Standard Specifications for Road and Bridge Construction, Edition of 2012 and Standard Drawings, Edition of 2012 with the 2012 Revision.

Contract ID: 153225 Page 48 of 97

Subsection	102.15 Process Agent.
Revision:	Replace the 1st paragraph with the following:
Kevision.	Every corporation doing business with the Department shall submit evidence of compliance with
	KRS Sections 14A.4-010, 271B.11-010, 271B.11-070, 271B.11-080, 271B.5-010 and 271B.16-
	220, and file with the Department the name and address of the process agent upon whom process
	may be served.
Subsection:	105.13 Claims Resolution Process.
Revision:	Delete all references to TC 63-34 and TC 63-44 from the subsection as these forms are no longer
Ke vision.	available through the forms library and are forms generated within the AASHTO SiteManager
	software.
Subsection:	108.03 Preconstruction Conference.
Revision:	Replace 8) Staking with the following:
ite vision.	8) Staking (designated by a Professional Engineer or Land Surveyor licensed in the
	Commonwealth of Kentucky.
Subsection:	109.07.02 Fuel.
Revision:	Revise item Crushed Aggregate Used for Embankment Stabilization to the following:
110 (151011)	Crushed Aggregate
	Used for Stabilization of Unsuitable Materials
	Used for Embankment Stabilization
	Delete the following item from the table.
	Crushed Sandstone Base (Cement Treated)
Subsection:	110.02 Demobilization.
Revision:	Replace the first part of the first sentence of the second paragraph with the following:
	Perform all work and operations necessary to accomplish final clean-up as specified in the first
	paragraph of Subsection 105.12;
Subsection:	112.03.12 Project Traffic Coordinator (PTC).
Revision:	Replace the last paragraph of this subsection with the following:
	Ensure the designated PTC has sufficient skill and experience to properly perform the task
	assigned and has successfully completed the qualification courses.
Subsection:	112.04.18 Diversions (By-Pass Detours).
Revision:	Insert the following sentence after the 2nd sentence of this subsection.
	The Department will not measure temporary drainage structures for payment when the contract
	documents provide the required drainage opening that must be maintained with the diversion.
	The temporary drainage structures shall be incidental to the construction of the diversion. If the
	contract documents fail to provide the required drainage opening needed for the diversion, the
	cost of the temporary drainage structure will be handled as extra work in accordance with section
	109.04.
	201.03.01 Contractor Staking.
Revision:	Replace the first paragraph with the following: Perform all necessary surveying under the
	general supervision of a Professional Engineer or Land Surveyor licensed in the Commonwealth
	of Kentucky.

Contract ID: 153225 Page 49 of 97

Subsections	201.04.01 Contractor Staking.
Revision:	_
Revision:	Replace the last sentence of the paragraph with the following: Complete the general layout of
	the project under the supervision of a Professional Engineer or Land Surveyor licensed in the
G 1 4	Commonwealth of Kentucky.
202200000	206.04.01 Embankment-in-Place.
Revision:	Replace the fourth paragraph with the following: The Department will not measure suitable
	excavation included in the original plans that is disposed of for payment and will consider it
	incidental to Embankment-in-Place.
	208.02.01 Cement.
Revision:	Replace paragraph with the following:
	Select Type I or Type II cement conforming to Section 801. Use the same type cement
	throughout the work.
	208.03.06 Curing and Protection.
Revision:	Replace the fourth paragraph with the following:
	Do not allow traffic or equipment on the finished surface until the stabilized subgrade has cured
	for a total of 7-days with an ambient air temperature above 40 degrees Fahrenheit. A curing day
	consists of a continuous 24-hour period in which the ambient air temperature does not fall below
	40 degrees Fahrenheit. Curing days will not be calculated consecutively, but must total seven (7)
	, 24-hour days with the ambient air temperature remaining at or above 40 degrees Fahrenheit
	before traffic or equipment will be allowed to traverse the stabilized subgrade. The Department
	may allow a shortened curing period when the Contractor requests. The Contractor shall give the
	Department at least 3 day notice of the request for a shortened curing period. The Department
	will require a minimum of 3 curing days after final compaction. The Contractor shall furnish
	cores to the treated depth of the roadbed at 500 feet intervals for each lane when a shortened
	curing time is requested. The Department will test cores using an unconfined compression test.
	Roadbed cores must achieve a minimum strength requirement of 80 psi.
Subsection:	208.03.06 Curing and Protection.
Revision:	Replace paragraph eight with the following:
	At no expense to the Department, repair any damage to the subgrade caused by freezing.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	A) Seed Mixtures for Permanent Seeding.
Revision:	Revise Seed Mix Type I to the mixture shown below:
	50% Kentucky 31 Tall Fescue (Festuca arundinacea)
	35% Hard Fescue (Festuca (Festuca longifolia)
	10% Ryegrass, Perennial (Lolium perenne)
	5% White Dutch Clover (Trifolium repens)
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	A) Seed Mixtures for Permanent Seeding.
Number:	2)
Revision:	Replace the paragraph with the following:
	Permanent Seeding on Slopes Greater than 3:1 in Highway Districts 4, 5, 6, and 7. Apply seed
	mix Type II at a minimum application rate of 100 pounds per acre. If adjacent to a golf course
	replace the crown vetch with Kentucky 31 Tall Fescue.

Contract ID: 153225 Page 50 of 97

	212.03.03 Permanent Seeding and Protection.
Part:	A) Seed Mixtures for Permanent Seeding.
Number:	3)
Revision:	Replace the paragraph with the following:
	Permanent Seeding on Slopes Greater than 3:1 in Highway Districts 1, 2, 3, 8, 9, 10, 11, and 12.
	Apply seed mix Type III at a minimum application rate of 100 pounds per acre. If adjacent to
	crop land or golf course, replace the Sericea Lespedeza with Kentucky 31 Fescue.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	B) Procedures for Permanent Seeding.
Revision:	Delete the first sentence of the section.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	B) Procedures for Permanent Seeding.
Revision:	Replace the second and third sentence of the section with the following:
	Prepare a seedbed and apply an initial fertilizer that contains a minimum of 100 pounds of
	nitrogen, 100 pounds of phosphate, and 100 pounds of potash per acre. Apply agricultural
	limestone to the seedbed when the Engineer determines it is needed. When required, place
	agricultural limestone at a rate of 3 tons per acre.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	D) Top Dressing.
Revision:	Change the title of part to D) Fertilizer.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	D) Fertilizer.
Revision:	Replace the first paragraph with the following:
	Apply fertilizer at the beginning of the seeding operation and after vegetation is established. Use
	fertilizer delivered to the project in bags or bulk. Apply initial fertilizer to all areas prior to the
	seeding or sodding operation at the application rate specified in 212.03.03 B). Apply 20-10-10
	fertilizer to the areas after vegetation has been established at a rate of 11.5 pounds per 1,000
	square feet. Obtain approval from the Engineer prior to the 2nd fertilizer application. Reapply
	fertilizer to any area that has a streaked appearance. The reapplication shall be at no additional
	cost to the Department. Re-establish any vegetation severely damaged or destroyed because of
	an excessive application of fertilizer at no cost to the Department.
Subsection:	212.03.03 Permanent Seeding and Protection.
Part:	D) Fertilizer.
Revision:	Delete the second paragraph.
Subsection:	212.04.04 Agricultural Limestone.
Revision:	Replace the entire section with the following:
	The Department will measure the quantity of agricultural limestone in tons.
Subsection:	212.04.05 Fertilizer.
Revision:	Replace the entire section with the following:
	The Department will measure fertilizer used in the seeding or sodding operations for payment.
	The Department will measure the quantity by tons.

Contract ID: 153225 Page 51 of 97

Subsection:	212.05 PAYMENT.						
Revision:	Delete the following item code:						
110 (151011)	Code Pay Item Pay Unit						
	05966 Topdressing Fertilizer Ton						
Subsection:	212.05 PAYMENT.						
Revision:	Add the following pay items:						
110 (101011)	Code Pay Item Pay Unit						
	05963 Initial Fertilizer Ton						
	05964 20-10-10 Fertilizer Ton						
	05992 Agricultural Limestone Ton						
Subsection:	213.03.02 Progress Requirements.						
Revision:	Replace the last sentence of the third paragraph with the following: Additionally, the						
	Department will apply a penalty equal to the liquidated damages when all aspects of work are not						
	coordinated in an acceptable manner within 7 calendar days after written notification.						
Subsection:	213.03.05 Temporary Control Measures.						
Part:	E) Temporary Seeding and Protection.						
Revision:	Delete the second sentence of the first paragraph.						
Subsection:	304.02.01 Physical Properties.						
Table:	Required Geogrid Properties						
Revision:	Replace all references to Test Method "GRI-GG2-87" with ASTM D 7737.						
Subsection:	402.03.02 Contractor Quality Control and Department Acceptance.						
Part:	B) Sampling.						
Revision:	Replace the second sentence with the following:						
	The Department will determine when to obtain the quality control samples using the random-						
	number feature of the mix design submittal and approval spreadsheet. The Department will						
	randomly determine when to obtain the verification samples required in Subsections 402.03.03						
	and 402.03.04 using the Asphalt Mixture Sample Random Tonnage Generator.						
	402.03.02 Contractor Quality Control and Department Acceptance.						
Part:	D) Testing Responsibilities.						
Number:	3) VMA.						
Revision:	Add the following paragraph below Number 3) VMA:						
	Retain the AV/VMA specimens and one additional corresponding G _{mm} sample for 5 working						
	days for mixture verification testing by the Department. For Specialty Mixtures, retain a mixture						
	sample for 5 working days for mixture verification testing by the Department. When the						
	Department's test results do not verify that the Contractor's quality control test results are within						
	the acceptable tolerances according to Subsection 402.03.03, retain the samples and specimens						
	from the affected sublot(s) for the duration of the project.						
	402.03.02 Contractor Quality Control and Department Acceptance.						
Part:	D) Testing Responsibilities.						
Number:	4) Density.						
Revision:	Replace the second sentence of the Option A paragraph with the following:						
	Perform coring by the end of the following work day.						

Contract ID: 153225 Page 52 of 97

Supplemental Specifications to the Standard Specifications for Road and Bridge Construction, 2012 Edition Effective with the July 31, 2015 Letting

402.03.02 Contractor Quality Control and Department Acceptance. **Subsection:** D) Testing Responsibilities. Part: Number: 5) Gradation. **Revision:** Delete the second paragraph. 402.03.02 Contractor Quality Control and Department Acceptance. **Subsection:** H) Unsatisfactory Work. Part: Number: 1) Based on Lab Data. **Revision:** Replace the second paragraph with the following: When the Engineer determines that safety concerns or other considerations prohibit an immediate shutdown, continue work and the Department will make an evaluation of acceptability according to Subsection 402.03.05. 402.03.03 Verification. **Subsection: Revision:** Replace the first paragraph with the following: **402.03.03 Mixture Verification.** For volumetric properties, the Department will perform a minimum of one verification test for AC, AV, and VMA according to the corresponding procedures as given in Subsection 402.03.02. The Department will randomly determine when to obtain the verification sample using the Asphalt Mixture Sample Random Tonnage Generator. For specialty mixtures, the Department will perform one AC and one gradation determination per lot according to the corresponding procedures as given in Subsection 402.03.02. However, Department personnel will not perform AC determinations according to KM 64-405. The Contractor will obtain a quality control sample at the same time the Department obtains the

402.03.02. If the Contractor's quality control sample is verified by the Department's test results within the tolerances provided below, the Contractor's sample will serve as the quality control sample for the affected sublot. The Department may perform the mixture verification test on the Contractor's equipment or on the Department's equipment.

Subsection:

402.03.03 Verification.

Part:

A) Evaluation of Sublot(s) Verified by Department.

Revision:

Replace the third sentence of the second paragraph with the following:

When the paired t-test indicates that the Contractor's data and Department's data are possibly not from the same population, the Department will investigate the cause for the difference according to Subsection 402.03.05 and implement corrective measures as the Engineer deems appropriate.

mixture verification sample and perform testing according to the procedures given in Subsection

Subsection:

402.03.03 Verification.

Part:

B) Evaluation of Sublots Not Verified by Department.

Revision:

Replace the third sentence of the first paragraph with the following:

When differences between test results are not within the tolerances listed below, the Department will resolve the discrepancy according to Subsection 402.03.05.

Contract ID: 153225 Page 53 of 97

Cubacations	402.03.03 Verification.
Part:	
	B) Evaluation of Sublots Not Verified by Department.
Revision:	Replace the third sentence of the second paragraph with the following:
	When the F -test or t -test indicates that the Contractor's data and Department's data are possibly
	not from the same population, the Department will investigate the cause for the difference
	according to Subsection 402.03.05 and implement corrective measures as the Engineer deems
	appropriate.
	402.03.03 Verification.
Part:	C) Test Data Patterns.
Revision:	Replace the second sentence with the following:
	When patterns indicate substantial differences between the verified and non-verified sublots, the
	Department will perform further comparative testing according to subsection 402.03.05.
	402.03 CONSTRUCTION.
Revision:	Add the following subsection: 402.03.04 Testing Equipment and Technician Verification.
	For mixtures with a minimum quantity of 20,000 tons and for every 20,000 tons thereafter, the
	Department will obtain an additional verification sample at random using the Asphalt Mixture
	Sample Random Tonnage Generator in order to verify the integrity of the Contractor's and
	Department's laboratory testing equipment and technicians. The Department will obtain a
	mixture sample of at least 150 lb at the asphalt mixing plant according to KM 64-425 and split it
	according to AASHTO R 47. The Department will retain one split portion of the sample and
	provide the other portion to the Contractor. At a later time convenient to both parties, the
	Department and Contractor will simultaneously reheat the sample to the specified compaction
	temperature and test the mixture for AV and VMA using separate laboratory equipment
	according to the corresponding procedures given in Subsection 402.03.02. The Department will
	evaluate the differences in test results between the two laboratories. When the difference
	between the results for AV or VMA is not within ± 2.0 percent, the Department will investigate
	and resolve the discrepancy according to Subsection 402.03.05.
Subsection:	402.03.04 Dispute Resolution.
Revision:	Change the subsection number to 402.03.05.
Subsection:	402.05 PAYMENT.
Part:	Lot Pay Adjustment Schedule Compaction Option A Base and Binder Mixtures
Table:	AC
Revision:	Replace the Deviation from JMF(%) that corresponds to a Pay Value of 0.95 to ±0.6.
Subsection:	403.02.10 Material Transfer Vehicle (MTV).
Revision:	Replace the first sentence with the following:
	In addition to the equipment specified above, provide a MTV with the following minimum
	characteristics:
Subsection:	412.02.09 Material Transfer Vehicle (MTV).
Revision:	Replace the paragraph with the following:
	Provide and utilize a MTV with the minimum characteristics outlined in section 403.02.10.
	2.10.100 and sample a 1/11, what are imministrated enductoristics outlined in section 103.02.10.

Contract ID: 153225 Page 54 of 97

Subsection:	412.03.07 Placement and Compaction.
Revision:	Replace the first paragraph with the following:
	Use a MTV when placing SMA mixture in the driving lanes. The MTV is not required on ramps
	and/or shoulders unless specified in the contract. When the Engineer determines the use of the
	MTV is not practical for a portion of the project, the Engineer may waive its requirement for that
	portion of pavement by a letter documenting the waiver.
Subsection:	412.04 MEASUREMENT.
Revision:	Add the following subsection:
	412.04.03. Material Transfer Vehicle (MTV). The Department will not measure the MTV for
	payment and will consider its use incidental to the asphalt mixture.
Subsection:	501.03.05 Weather Limitations and Protection.
Revision:	Replace the reference to Subsection 501.03.19 in Paragraph 5, with Subsection 501.03.20.
Subsection:	501.03.19 Surface Tolerances and Testing Surface.
Part:	B) Ride Quality.
Revision:	Add the following to the end of the first paragraph:
	The Department will specify if the ride quality requirements are Category A or Category B when
	ride quality is specified in the Contract. Category B ride quality requirements shall apply when
	the Department fails to classify which ride quality requirement will apply to the Contract.
Subsection:	603.03.06 Cofferdams.
Revision:	Replace the seventh sentence of paragraph one with the following:
	Submit drawings that are stamped by a Professional Engineer licensed in the Commonwealth of
	Kentucky.
	605.03.04 Tack Welding.
Revision:	Insert the subsection and the following:
	605.03.04 Tack Welding. The Department does not allow tack welding.
	606.03.17 Special Requirements for Latex Concrete Overlays.
Part:	A) Existing Bridges and New Structures.
Number:	1) Prewetting and Grout-Bond Coat.
Revision:	Add the following sentence to the last paragraph: Do not apply a grout-bond coat on bridge
	decks prepared by hydrodemolition.
	609.03 Construction.
Revision:	Replace Subsection 609.03.01 with the following:
	609.03.01 A) Swinging the Spans. Before placing concrete slabs on steel spans or precast
	concrete release the temporary erection supports under the bridge and swing the span free on its
	supports.
	609.03.01 B) Lift Loops. Cut all lift loops flush with the top of the precast beam once the beam
	is placed in the final location and prior to placing steel reinforcement. At locations where lift
	loops are cut, paint the top of the beam with galvanized or epoxy paint.

Contract ID: 153225 Page 55 of 97

Subsection:	611.03.02 Precast Unit Construction.
Revision:	Replace the first sentence of the subsection with the following:
	Construct units according to ASTM C1577, replacing Table 1 (Design Requirements for
	Precast Concrete Box Sections Under Earth, Dead and HL-93 Live Load Conditions) with
	KY Table 1 (Precast Culvert KYHL-93 Design Table), and Section 605 with the following
	exceptions and additions:
Subsection:	613.03.01 Design.
Number:	2)
Revision:	Replace "AASHTO Standard Specifications for Highway Bridges" with "AASHTO LRFD
The vision.	Bridge Design Specifications"
Subsection:	615.06.02
Revision:	Add the following sentence to the end of the subsection.
The vision.	The ends of units shall be normal to walls and centerline except exposed edges shall be beveled
	34 inch.
Subsection:	615.06.03 Placement of Reinforcement in Precast 3-Sided Units.
Revision:	Replace the reference of 6.6 in the section to 615.06.06.
	615.06.04 Placement of Reinforcement for Precast Endwalls.
Revision:	Replace the reference of 6.7 in the section to 615.06.07.
	615.06.06 Laps, Welds, and Spacing for Precast 3-Sided Units.
Revision:	Replace the subsection with the following:
	Tension splices in the circumferential reinforcement shall be made by lapping. Laps may not be
	tack welded together for assembly purposes. For smooth welded wire fabric, the overlap shall
	meet the requirements of AASHTO 2012 Bridge Design Guide Section 5.11.2.5.2 and AASHTO
	2012 Bridge Design Guide Section 5.11.6.3. For deformed welded wire fabric, the overlap shall
	meet the requirements of AASHTO 2012 Bridge Design Guide Section 5.11.2.5.1 and AASHTO
	2012 Bridge Design Guide Section 5.11.6.2. The overlap of welded wire fabric shall be measured
	between the outer most longitudinal wires of each fabric sheet. For deformed billet-steel bars,
	the overlap shall meet the requirements of AASHTO 2012 Bridge Design Guide Section
	5.11.2.1. For splices other than tension splices, the overlap shall be a minimum of 12" for welded
	wire fabric or deformed billet-steel bars. The spacing center to center of the circumferential wires
	in a wire fabric sheet shall be no less than 2 inches and no more than 4 inches. The spacing
	center to center of the longitudinal wires shall not be more than 8 inches. The spacing center to
	center of the longitudinal distribution steel for either line of reinforcing in the top slab shall be
	not more than 16 inches.
Subsection:	615.06.07 Laps, Welds, and Spacing for Precast Endwalls.
Revision:	Replace the subsection with the following:
	Splices in the reinforcement shall be made by lapping. Laps may not be tack welded together for
	assembly purposes. For smooth welded wire fabric, the overlap shall meet the requirements of
	AASHTO 2012 Bridge Design Guide Section 5.11.2.5.2 and AASHTO 2012 Bridge Design
	Guide Section 5.11.6.3. For deformed welded wire fabric, the overlap shall meet the
	requirements of AASHTO 2012 Bridge Design Guide Section 5.11.2.5.1 and AASHTO 2012
	Bridge Design Guide Section 5.11.6.2. For deformed billet-steel bars, the overlap shall meet the
	requirements of AASHTO 2012 Bridge Design Guide Section 5.11.2.1. The spacing center-to-
	center of the wire fabric sheet shall not be less than 2 inches or more than 8 inches.

Contract ID: 153225 Page 56 of 97

Subsection: Revision: Replace the subsection with the following: Start-up slump, air content, unit weight, and temperature tests will be performed each day on the first batch of concrete. Acceptable start-up results are required for production of the first unit. After the first unit has been established, random acceptance testing is performed daily for each 50 yd³ (or fraction thereof). In addition to the slump, air content, unit weight, and temperature tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Delete the second sentence. Subsection: 615.08.04 Acceptability of Core Tests. Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Revision: Revision: Replace bullet 5) with the following: Conform to Section 821. Subsection: 716.03.03 CIsphting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the third sentence with the following: Orient the transformer base so the door is
Start-up slump, air content, unit weight, and temperature tests will be performed each day on the first batch of concrete. Acceptable start-up results are required for production of the first unit. After the first unit has been established, random acceptance testing is performed daily for each 50 yd³ (or fraction thereof). In addition to the slump, air content, unit weight, and temperature tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Revision: Delete the second sentence. Subsection: Revision: Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: Revision: Nevision: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: Revision: Replace sentence with the following: Conform to Section 821. Subsection: Replace sentence with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Revision: Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Revision: After the first unit weight, and temperature tests. A) Conventional Installation.
first batch of concrete. Acceptable start-up results are required for production of the first unit. After the first unit has been established, random acceptance testing is performed daily for each 50 yd³ (or fraction thereof). In addition to the slump, air content, unit weight, and temperature tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Bevision: Delete the second sentence. Subsection: 615.08.04 Acceptability of Core Tests. Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: Replace sentence with the following: Conform to Section 821. Subsection: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
After the first unit has been established, random acceptance testing is performed daily for each 50 yd³ (or fraction thereof). In addition to the slump, air content, unit weight, and temperature tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Delete the second sentence. Subsection: 615.12 Inspection. Revision: Delete the entire subsection. Subsection: 615.12 Inspection. Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims. Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
50 yd³ (or fraction thereof). In addition to the slump, air content, unit weight, and temperature tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing.
tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Delete the second sentence. Subsection: 615.08.04 Acceptability of Core Tests. Delete the entire subsection. Subsection: 615.12 Inspection. Revision: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims. Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
tests, a minimum of one set of cylinders shall be required each time plastic property testing is performed. Subsection: 615.08.02 Compression Testing. Delete the second sentence. Subsection: 615.08.04 Acceptability of Core Tests. Delete the entire subsection. Subsection: 615.12 Inspection. Revision: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims. Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: Revision: Delete the second sentence. Subsection: Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Wetucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: Revision: Tol.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: Revision: Revision: Replace sentence with the following: Conform to Section 821. Subsection: Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: Part: A) Conventional Installation.
Revision: Delete the second sentence. Subsection: 615.08.04 Acceptability of Core Tests. Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: Revision: Delete the entire subsection. Subsection: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: Revision: Revision: Revision: Revision: Replace sentence with the following: Conform to Section 821. Subsection: Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: Replace the second sentence with the following: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: Part: A) Conventional Installation.
Revision: Delete the entire subsection. Subsection: Revision: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: 716.03.02 Lighting Standard Installation. A) Conventional Installation.
Subsection: Revision: Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: Revision: Revision: Revision: Replace sentence with the following: Conform to Section 821. Subsection: Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Revision: Replace the second sentence with the following: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: Ret: A) Conventional Installation. A) Conventional Installation.
Add the following sentences to the end of the subsection: Units will arrive at jobsite with the "Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: Replace sentence with the following: Conform to Section 821. Subsection: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
"Kentucky Oval" stamped on the unit which is an indication of acceptable inspection at the production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
production facility. Units shall be inspected upon arrival for any evidence of damage resulting from transport to the jobsite. Subsection: 701.04.16 Deduction for Pipe Deflection. Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
from transport to the jobsite. Subsection: Revision: Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: Revision: Revision: Replace sentence with the following: Conform to Section 821. Subsection: Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: Revision: Revision: Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: A) Conventional Installation.
Subsection: 701.04.16 Deduction for Pipe Deflection. Revision: Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Revision: Insert the following at the end of the paragraph: The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
The section length is determined by the length of the pipe between joints where the failure occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
occurred. Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
 Subsection: 716.02.02 Paint. Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Revision: Replace sentence with the following: Conform to Section 821. Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: 716.03 CONSTRUCTION. Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Revision: Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: T16.03.02 Lighting Standard Installation. Revision: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: T16.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
interims, Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: 716.03.02 Lighting Standard Installation. Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Revision: Replace the second sentence with the following: Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. A) Conventional Installation.
Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. A) Conventional Installation.
of four feet from the front face of the guardrail to the front face of the pole base. Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Subsection: 716.03.02 Lighting Standard Installation. Part: A) Conventional Installation.
Part: A) Conventional Installation.
Revision: Replace the third sentence with the following: Orient the transformer base so the door is
positioned on the side away from on-coming traffic.
Subsection: 716.03.02 Lighting Standard Installation.
Part: A) Conventional Installation.
Number: 1) Breakaway Installation and Requirements.
Revision: Replace the first sentence with the following: For breakaway supports, conform to Section 12 of
the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires,
and Traffic Signals, 2013-6th Edition with current interims.
Subsection: 716.03.02 Lighting Standard Installation.
Haute III) Lich Mast Installation
Part: B) High Mast Installation Revision: Replace the first sentence with the following: Install each high mast pole as noted on plans.

Contract ID: 153225 Page 57 of 97

Supplemental Specifications to the Standard Specifications for Road and Bridge Construction, 2012 Edition Effective with the July 31, 2015 Letting

Subsection: 716.03.02 Lighting Standard Installation.

Part: B) High Mast Installation Number: 2) Concrete Base Installation

Revision: Modification of Chart and succeeding paragraphs within this section:

Drilled	Drilled Shaft Depth Data								
		3:1 Ground		2:1 (round	1.5:1 Ground			
Level	Ground Slope Slope		ope Slo		pe ⁽²⁾				
Soil	Rock	Soil	Rock	Soil	Rock	Soil	Rock		
17 ft	7 f t	19 ft	7 f t	20 ft	7 f t	(1)	7 ft		

Steel Requirements								
Vert	ical Bars	Ties	s or Spiral					
Size			Spacing or					
Size	Total	Size	Pitch					
#10	16	#4	12 inch					

- (1): Shaft length is 22' for cohesive soil only. For cohesionless soil, contact geotechnical branch for design.
- (2): Do not construct high mast drilled shafts on ground slopes steeper than 1.5:1 without the approval of the Division of Traffic.

If rock is encountered during drilling operations and confirmed by the engineer to be of sound quality, the shaft is only required to be further advanced into the rock by the length of rock socket shown in the table. The total length of the shaft need not be longer than that of soil alone. Both longitudinal rebar length and number of ties or spiral length shall be adjusted accordingly.

If a shorter depth is desired for the drilled shaft, the contractor shall provide, for the state's review and approval, a detailed column design with individual site specific soil and rock analysis performed and approved by a Professional Engineer licensed in the Commonwealth of Kentucky.

Spiral reinforcement may be substituted for ties. If spiral reinforcement is used, one and onehalf closed coils shall be provided at the ends of each spiral unit. Subsurface conditions consisting of very soft clay or very loose saturated sand could result in soil parameters weaker than those assumed. Engineer shall consult with the geotechnical branch if such conditions are encountered.

The bottom of the drilled hole shall be firm and thoroughly cleaned so no loose or compressible materials are present at the time of the concrete placement. If the drilled hole contains standing water, the concrete shall be placed using a tremie to displace water. Continuous concrete flow will be required to insure full displacement of any water.

The reinforcement and anchor bolts shall be adequately supported in the proper positions so no movement occurs during concrete placement. Welding of anchor bolts to the reinforcing cage is unacceptable, templates shall be used. Exposed portions of the foundation shall be formed to create a smooth finished surface. All forming shall be removed upon completion of foundation construction.

Subsection: 716.03.03 Trenching.

Part:

A) Trenching of Conduit for Highmast Ducted Cables.

Revision:

Add the following after the first sentence: If depths greater than 24 inches are necessary, obtain the Engineer's approval and maintain the required conduit depths coming into the junction boxes. No payment for additional junction boxes for greater depths will be allowed.

Contract ID: 153225 Page 58 of 97

Subsection:	716.03.03 Trenching.		
Part:	B) Trenching of Conduit for Non-Highmast Cables.		
Revision:	Add the following after the second sentence: If depths greater than 24 inches are necessary for		
	either situation listed previously, obtain the Engineer's approval and maintain the required		
	conduit depths coming into the junction boxes. No payment for additional junction boxes for		
	greater depths will be allowed.		
Subsection:	716.03.10 Junction Boxes.		
Revision:	Replace subsection title with the following: Electrical Junction Box.		
Subsection:	716.04.07 Pole with Secondary Control Equipment.		
Revision:	Replace the paragraph with the following:		
	The Department will measure the quantity as each individual unit furnished and installed. The		
	Department will not measure mounting the cabinet to the pole, backfilling, restoration, any		
	necessary hardware to anchor pole, or electrical inspection fees, and will consider them		
	incidental to this item of work. The Department will also not measure furnishing and installing		
	electrical service conductors, specified conduits, meter base, transformer, service panel, fused		
	cutout, fuses, lighting arrestors, photoelectrical control, circuit breaker, contactor, manual switch,		
	ground rods, and ground wires and will consider them incidental to this item of work.		
Subsection:	716.04.08 Lighting Control Equipment.		
Revision:	Replace the paragraph with the following:		
	The Department will measure the quantity as each individual unit furnished and installed. The		
	Department will not measure constructing the concrete base, excavation, backfilling, restoration,		
	any necessary anchors, or electrical inspection fees, and will consider them incidental to this item		
	of work. The Department will also not measure furnishing and installing electrical service		
	conductors, specified conduits, meter base, transformer, service panel, fused cutout, fuses,		
	lighting arrestors, photoelectrical control, circuit breakers, contactor, manual switch, ground		
	rods, and ground wires and will consider them incidental to this item of work.		
	716.04.09 Luminaire.		
Revision:	Replace the first sentence with the following:		
	The Department will measure the quantity as each individual unit furnished and installed.		
	716.04.10 Fused Connector Kits.		
Revision:	Replace the first sentence with the following:		
	The Department will measure the quantity as each individual unit furnished and installed.		
	716.04.13 Junction Box.		
Revision:	Replace the subsection title with the following: Electrical Junction Box Type Various.		
Subsection:	716.04.13 Junction Box.		
Part:	A) Junction Electrical.		
Revision:	Rename A) Junction Electrical to the following: A) Electrical Junction Box.		
	716.04.14 Trenching and Backfilling.		
Revision:	Replace the second sentence with the following:		
	The Department will not measure excavation, backfilling, underground utility warning tape (if		
	required), the restoration of disturbed areas to original condition, and will consider them		
	incidental to this item of work.		

Contract ID: 153225 Page 59 of 97

Subsection	716.04.18 Remove Lighting.	\neg	
Revision:	Replace the paragraph with the following:		
Kevision.			
	The Department will measure the quantity as a lump sum for the removal of lighting equipment.		
	The Department will not measure the disposal of all equipment and materials off the project by		
	the contractor. The Department also will not measure the transportation of the materials and will consider them incidental to this item of work.		
Cubaatian	716.04.20 Bore and Jack Conduit.		
Revision:	Replace the paragraph with the following: The Department will measure the quantity in linear		
Revision:			
	feet. This item shall include all work necessary for boring and installing conduit under an existing roadway. Construction methods shall be in accordance with Sections 706.03.02,		
	paragraphs 1, 2, and 4.		
Subsection	716.05 PAYMENT.		
Revision:	Replace items 04810-04811, 20391NS835 and, 20392NS835 under Code, Pay Item, and Pay		
Kevision:	Unit with the following:		
	Ome with the following.		
	Code Pay Item Pay Unit		
	04810 Electrical Junction Box Each		
	04811 Electrical Junction Box Type B Each		
	20391NS835 Electrical Junction Box Type A Each		
	20392NS835 Electrical Junction Box Type C Each		
Subsection:	723.02.02 Paint.		
Revision:	Replace sentence with the following: Conform to Section 821.		
	723.03 CONSTRUCTION.		
Revision:	Replace bullet 5) with the following: 5) AASHTO Standard Specifications for Structural		
	Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current		
	interims,		
Subsection:	723.03.02 Poles and Bases Installation.		
Revision:	Replace the first sentence with the following:		
	Regardless of the station and offset noted, locate all poles/bases behind the guardrail a minimum		
	of four feet from the front face of the guardrail to the front face of the pole base.		
Subsection:	723.03.02 Poles and Bases Installation.		
Part:	A) Steel Strain and Mastarm Poles Installation		
Revision:	Replace the second paragraph with the following: For concrete base installation, see Section		
	716.03.02, B), 2), Paragraphs 2-7. Drilled shaft depth shall be based on the soil conditions		
	encountered during drilling and slope condition at the site. Refer to the design chart below:		
Subsection:	723.03.02 Poles and Bases Installation.		
Part:	B) Pedestal or Pedestal Post Installation.		
Revision:	Replace the fourth sentence of the paragraph with the following: For breakaway supports,		
	conform to Section 12 of the AASHTO Standard Specifications for Structural Supports for		
	Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims.		

a	700 00 00 F		
Part:	A) Under Roadway.		
Revision:	Add the following after the second sentence: If depths greater than 24 inches are necessary, obtain the Engineer's approval and maintain ether required conduit depths coming into the		
	obtain the Engineer's approval and maintain ether required conduit depths coming into the		
	junction boxes. No payment for additional junction boxes for greater depths will be allowed.		
Subsection:	723.03.11 Wiring Installation.		
Revision:	Add the following sentence between the fifth and sixth sentences: Provide an extra two feet of		
	loop wire and lead-in past the installed conduit in poles, pedestals, and junction boxes.		
Subsection:	723.03.12 Loop Installation.		
Revision:	Replace the fourth sentence of the 2nd paragraph with the following: Provide an extra two feet of		
	loop wire and lead-in past the installed conduit in poles, pedestals, and junction boxes.		
Subsection:	723.04.02 Junction Box.		
Revision:	Replace subsection title with the following: Electrical Junction Box Type Various.		
Subsection:	723.04.03 Trenching and Backfilling.		
Revision:	Replace the second sentence with the following: The Department will not measure excavation,		
	backfilling, underground utility warning tape (if required), the restoration of disturbed areas to		
	original condition, and will consider them incidental to this item of work.		
Subsection:	723.04.10 Signal Pedestal.		
Revision:	: Replace the second sentence with the following: The Department will not measure excavation		
	concrete, reinforcing steel, specified conduits, fittings, ground rod, ground wire, backfilling,		
	restoring disturbed areas, or other necessary hardware and will consider them incidental to this		
	item of work.		
	723.04.15 Loop Saw Slot and Fill.		
Revision:	Replace the second sentence with the following: The Department will not measure sawing,		
	cleaning and filling induction loop saw slot, loop sealant, backer rod, and grout and will cons		
	them incidental to this item of work.		
	723.04.16 Pedestrian Detector.		
Revision:	Replace the paragraph with the following: The Department will measure the quantity as each		
	individual unit furnished, installed and connected to pole/pedestal. The Department will not		
	measure installing R10-3e (with arrow) sign, furnishing and installing mounting hardware for		
	sign and will consider them incidental to this item of work.		
	723.04.18 Signal Controller- Type 170.		
Revision:	Replace the second sentence with the following: The Department will not measure constructing		
	the concrete base or mounting the cabinet to the pole, connecting the signal and detectors,		
	excavation, backfilling, restoration, any necessary pole mounting hardware, electric service, or		
	electrical inspection fees and will consider them incidental to this item of work. The Department		
	will also not measure furnishing and connecting the induction of loop amplifiers, pedestrian		
	isolators, load switches, model 400 modem card; furnishing and installing electrical service		
	conductors, specified conduits, anchors, meter base, fused cutout, fuses, ground rods, ground		
	wires and will consider them incidental to this item of work.		

Contract ID: 153225 Page 61 of 97

Subsection:	723.04.20 Install Signal Controller - Type 170.			
Revision:	Replace the paragraph with the following: The Department will measure the quantity as each			
	individual unit installed. The Department will not measure constructing the concrete base or			
	mounting the cabinet to the pole, connecting the signal and detectors, and excavation,			
	backfilling, restoration, any necessary pole mounting hardware, electric service, or electrical inspection fees and will consider them incidental to this item of work. The Department will also			
	not measure connecting the induction loop amplifiers, pedestrian, isolators, load switches, model			
	400 modem card; furnishing and installing electrical service conductors, specified conduits,			
	anchors, meter base, fused cutout, fuses, ground rods, ground wires and will consider them			
	incidental to this item of work.			
Subsection:	723.04.22 Remove Signal Equipment.			
Revision:	Replace the paragraph with the following: The Department will measure the quantity as a lump			
	sum removal of signal equipment. The Department will not measure the return of control			
	equipment and signal heads to the Department of Highways as directed by the District Traffic			
	Engineer. The Department also will not measure the transportation of materials of the disposal			
	of all other equipment and materials off the project by the contractor and will consider them			
	incidental to this item of work.			
Subsection:	723.04.28 Install Pedestrian Detector Audible.			
Revision:	Replace the second sentence with the following: The Department will not measure installing sign			
	R10-3e (with arrow) and will consider it incidental to this item of work.			
Subsection:	723.04.29 Audible Pedestrian Detector.			
Revision:	Replace the second sentence with the following: The Department will not measure furnishing			
	and installing the sign R10-3e (with arrow) and will consider it incidental to this item of work.			
Subsection:	723.04.30 Bore and Jack Conduit.			
Revision:	Replace the paragraph with the following: The Department will measure the quantity in linear			
	feet. This item shall include all work necessary for boring and installing conduit under an			
	existing roadway. Construction methods shall be in accordance with Sections 706.03.02,			
	paragraphs 1, 2, and 4.			
Subsection:	723.04.31 Install Pedestrian Detector.			
Revision:	Replace the paragraph with the following: The Department will measure the quantity as each			
	individual unit installed and connected to pole/pedestal. The Department will not measure			
	installing sign R 10-3e (with arrow) and will consider it incidental to this item of work.			
	723.04.32 Install Mast Arm Pole.			
Revision:	Replace the second sentence with the following: The Department will not measure arms, signal			
	mounting brackets, anchor bolts, or any other necessary hardware and will consider them			
	incidental to this item of work.			
	723.04.33 Pedestal Post.			
Revision:	Replace the second sentence with the following: The Department will not measure excavation,			
	concrete, reinforcing steel, anchor bolts, conduit, fittings, ground rod, ground wire, backfilling,			
	restoration, or any other necessary hardware and will consider them incidental to this item of			
	work.			

Contract ID: 153225 Page 62 of 97

Subsection	723 04 36 Traffi	ic Signal Pole Rase			
Revision:	723.04.36 Traffic Signal Pole Base. Replace the second contains with the following: The Department will not measure everytion.				
Revision:	Replace the second sentence with the following: The Department will not measure excavation,				
	reinforcing steel, anchor bolts, specified conduits, ground rods, ground wires, backfilling, or restoration and will consider them incidental to this item of work.				
C14:			sitem of work.		
		l Signal Pedestal.	D		
Revision:			ne Department will not measure excavation,		
		_	conduits, fittings, ground rod, ground wire,		
	backfilling, restoration, or any other necessary hardware and will consider them incidental to this item of work.				
G 1 4		1D 1 (1D)			
	723.04.38 Instal		D ('11)		
Revision:	-	_	ne Department will not measure excavation,		
		_	conduits, fittings, ground rod, ground wire,		
	backfilling, restoration, or any other necessary hardware and will consider them incidental to this				
G 1	item of work.				
	723.05 PAYME		202NG025 do., C. do. D Ido., d. D		
Revision:	1 *		392NS835 under <u>Code</u> , <u>Pay Item</u> , and <u>Pay</u>		
	Unit with the fol	nowing:			
	C- 1-	D I/	D II		
	Code	Pay Item	Pay Unit		
	04810	Electrical Junction Box	Each		
	04811	Electrical Junction Box Type B	Each		
	20391NS835	Electrical Junction Box Type A	Each		
C14:	20392NS835	Electrical Junction Box Type C	Each		
	804.01.02 Crush				
Revision:		ence of the section.			
	804.01.06 Slag.	1 6-11			
Revision:		and following sentence.	h - D		
			he Department will allow steel slag sand only		
C14:	in asphalt surfac	11			
Revision:	804.04 Asphalt	section with the following:			
Revision:	1	E	man alog and with the addition of filler as		
	Provide natural, crushed, conglomerate, or blast furnace slag sand, with the addition of filler as				
	necessary, to meet gradation requirements. The Department will allow any combination of				
	natural, crushed, conglomerate or blast furnace slag sand when the combination is achieved us				
Subsection:	cold feeds at the plant. The Engineer may allow other fine aggregates.				
Revision:	806.03.01 General Requirements. Replace the second sentence of the paragraph with the following:				
Kevisioii:					
	Additionally, the material must have a minimum solubility of 99.0 percent when tested according				
	to AASHTO T 44 and PG 76-22 must exhibit a minimum recovery of 60 percent, with a J _{NR}				
	(nonrecoverable creep compliance) between 0.1 and 0.5, when tested according to AASHTO TP				
	70.				

Contract ID: 153225 Page 63 of 97

Subsection:	806.03.01 General Requirements.				
Table:	PG Binder Requirements and Price Adjustment Schedule				
Revision:	Replace the Elastic Recovery, % (3) (AASHTO T301) and all corresponding values in the table				
	with the following:				
	Test Specification 100% Pay 90% Pay 80% Pay 70% Pay 50% Pay 100% P				
	MSCR recovery, $\%^{(3)}$ 60 Min. ≥58 56 55 54 <53				
	(AASHTO TP 70)				
	806.03.01 General Requirements.				
Table:	PG Binder Requirements and Price Adjustment Schedule				
Superscript:	(3)				
Revision:	Replace (3) with the following:				
	Perform testing at 64°C.				
Subsection:	813.04 Gray Iron Castings.				
Revision:	Replace the reference to "AASHTO M105" with "ASTM A48".				
Subsection:	813.09.02 High Strength Steel Bolts, Nuts, and Washers.				
Number:	A) Bolts.				
Revision:	Delete first paragraph and "Hardness Number" Table. Replace with the following:				
	A) Bolts. Conform to ASTM A325 (AASHTO M164) or ASTM A490 (AASHTO 253) as				
	applicable.				
	814.04.02 Timber Guardrail Posts.				
Revision:	Third paragraph, replace the reference to "AWPA C14" with "AWPA U1, Section B, Paragraph				
	4.1".				
	814.04.02 Timber Guardrail Posts.				
Revision:	Replace the first sentence of the fourth paragraph with the following:				
	Use any of the species of wood for round or square posts covered under AWPA U1.				
	814.04.02 Timber Guardrail Posts.				
Revision:	Fourth paragraph, replace the reference to "AWPA C2" with "AWPA U1, Section B, Paragraph				
	4.1".				
	814.04.02 Timber Guardrail Posts.				
Revision:	Delete the second sentence of the fourth paragraph.				
	814.05.02 Composite Plastic.				
Revision:	1) Add the following to the beginning of the first paragraph: Select composite offset blocks				
	conforming to this section and assure blocks are from a manufacturer included on the				
	Department's List of Approved Materials.				
Subsection:	2) Delete the last paragraph of the subsection. 816.07.02 Wood Posts and Braces.				
Revision:	First paragraph, replace the reference to "AWPA C5" with "AWPA U1, Section B, Paragraph				
AC VISIUII.	4.1".				
Subsection:	816.07.02 Wood Posts and Braces.				
Revision:	Delete the second sentence of the first paragraph.				
	818.07 Preservative Treatment.				
Revision:	First paragraph, replace all references to "AWPA C14" with "AWPA U1, Section A".				
	r				

Contract ID: 153225 Page 64 of 97

Subsection:	834.14 Lighting Poles.			
Revision:	Replace the first sentence with the following: Lighting pole design shall be in accordance with			
	loading and allowable stress requirements of the AASHTO Standard Specifications for Structural			
	Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims, with the exception of the following: The Cabinet will waive the requirement stated in			
	interims, with the exception of the following: The Cabinet will waive the requirement stated in the first sentence of Section 5.14.6.2 – Reinforced Holes and Cutouts for high mast poles (only).			
	the first sentence of Section 5.14.6.2 – Reinforced Holes and Cutouts for high mast poles (only). The minimum diameter at the base of the pole shall be 22 inches for high mast poles (only).			
	The minimum diameter at the base of the pole shall be 22 inches for high mast poles (only).			
Subsection	834.14.03 High Mast Poles.			
Revision:	Remove the second and fourth sentence from the first paragraph.			
Subsection	834.14.03 High Mast Poles.			
Revision:	Replace the third paragraph with the following: Provide calculations and drawings that are			
	stamped by a Professional Engineer licensed in the Commonwealth of Kentucky.			
	834.14.03 High Mast Poles.			
Revision:	Replace paragraph six with the following: Provide a pole section that conforms to ASTM A 595			
	grade A with a minimum yield strength of 55 KSI or ASTM A 572 with a minimum yield			
	strength of 55 KSI. Use tubes that are round or 16 sided with a four inch corner radius, have a			
	constant linear taper of .144 in/ft and contain only one longitudinal seam weld. Circumferential			
	welded tube butt splices and laminated tubes are not permitted. Provide pole sections that are			
	telescopically slip fit assembled in the field to facilitate inspection of interior surface welds and			
	the protective coating. The minimum length of the telescopic slip splices shall be 1.5 times the inside diameter of the exposed end of the female section. Use longitudinal seam welds as			
	inside diameter of the exposed end of the female section. Use longitudinal seam welds as commended in Section 5.15 of the AASHTO 2013 Specifications. The thickness of the			
	-			
	transverse base shall not be less than 2 inches. Plates shall be integrally welded to the tubes with			
	a telescopic welded joint or a full penetration groove weld with backup bar. The handhole cover shall be removable from the handhole frame. One the frame side opposite the hinge, provide a			
	mechanism on the handhole cover/frame to place the Department's standard padlock as specified			
	in Section 834.25. The handhole frame shall have two stainless studs installed opposite the hinge			
	to secure the handhole cover to the frame which includes providing stainless steel wing nuts and			
	washers. The handhole cover shall be manufactured from 0.25 inch thick galvanized steel			
	(ASTM A 153) and have a neoprene rubber gasket that is permanently secured to the handhole			
	frame to insure weather-tight protection. The hinge shall be manufactured from 7-guage			
	stainless steel to provide adjustability to insure weather-tight fit for the cover. The minimum			
	clear distance between the transverse plate and the bottom opening of the handhole shall not be			
	less than the diameter of the bottom tube of the pole but needs to be at least 15 inches. Provide			
	products that are hot-dip galvanized to the requirements of either ASTM A123 (fabricated			
	products) or ASTM A 153 (hardware items).			
Subsection:	834.16 ANCHOR BOLTS.			
Revision:	Insert the following sentence at the beginning of the paragraph: The anchor bolt design shall			
	follow the NCHRP Report 494 Section 2.4 and NCHRP 469 Appendix A Specifications.			

Contract ID: 153225 Page 65 of 97

Subsection:	834.17.01 Conventional.		
Revision:	Add the following sentence after the second sentence: Provide a waterproof sticker mounted on		
	the bottom of the housing that is legible from the ground and indicates the wattage of the fixture		
	by providing the first two numbers of the wattage.		
Subsection:	· · ·		
Revision:	Replace the last five sentences in the second paragraph with the following sentences:		
	Provide a cabinet door with a louvered air vent, filter-retaining brackets and an easy to clean		
	metal filter. Provide a cabinet door that is keyed with a factory installed standard no. 2 corbin		
	traffic control key. Provide a light fixture with switch and bulb. Use a 120-volt fixture and		
	utilize a L.E.D. bulb (equivalent to 60 watts minimum). Fixture shall be situated at or near the		
	top of the cabinet and illuminate the contents of the cabinet. Provide a 120 VAC GFI duple		
	receptacle in the enclosure with a separate 20 amp breaker.		
	The state of the s		
Subsection:	835.07 Traffic Poles.		
Revision:	Replace the first sentence of the first paragraph with the following: Pole diameter and wall		
	thickness shall be calculated in accordance with the AASHTO Standard Specifications for		
	Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 2013-6th Edition with		
	current interims.		
Subsection:	835.07 Traffic Poles.		
Revision:	*Replace the first sentence of the fourth paragraph with the following: Ensure transverse plates		
	have a thickness ≥ 2 inches.		
	*Add the following sentence to the end of the fourth paragraph: The bottom pole diamet		
	not be less than 16.25 inches.		
Subsection:			
Revision:	Replace the third sentence of the fifth paragraph with the following: For anchor bolt design, pole		
	forces shall be positioned in such a manner to maximize the force on any individual anchor bolt		
	regardless of the actual anchor bolt orientation with the pole.		
Subsection:	835.07 Traffic Poles.		
Revision:	Replace the first and second sentence of the sixth paragraph with the following:		
	The pole handhole shall be 25 inches by 6.5 inches. The handhole cover shall be removable		
	from the handhole frame. On the frame side opposite the hinge, provide a mechanism on the		
	handhole cover/frame to place the Department's standard padlock as specified in Section 834.25.		
	The handhole frame shall have two stainless studs installed opposite the hinge to secure the		
	handhole cover to the frame which includes providing stainless steel wing nuts and washers. The		
	handhole cover shall be manufactured from 0.25 inch thick galvanized steel (ASTM 153) and		
	have a neoprene rubber gasket that is permanently secured to the handhole frame to insure		
	weather-tight protection. The hinge shall be manufactured from 7 gauge stainless steel to		
	provide adjustability to insure a weather-tight fit for the cover. The minimum clear distance		
	between the transverse plate and the bottom opening of the handhole shall not be less than the		
	diameter of the bottom tube but needs to be at least 12 inches.		
<u> </u>	<u> </u>		

Contract ID: 153225 Page 66 of 97


Subsection:	835.07 Traffic Poles.		
Revision:	*Replace the first sentence of the last paragraph with the following: Provide calculations and		
ite vision.	drawings that are stamped by a Professional Engineer licensed in the Commonwealth of		
	Kentucky.		
	*Replace the third sentence of the last paragraph with the following: All tables referenced in		
	835.07 are found in the AASHTO Standard Specifications for Structural Supports for Highway		
	Signs, Luminaires, and Traffic Signals, 2013-6th Edition with current interims.		
Subsection:	835.07.01 Steel Strain Poles.		
	Replace the second sentence of the second paragraph with the following:		
	The detailed analysis shall be certified by a Professional Engineer licensed in the Commonwealth		
	of Kentucky.		
Subsection:	835.07.01 Steel Strain Poles.		
	Replace number 7. after the second paragraph with the following: 7. Fatigue calculations should		
	be shown for all fatigue related connections. Provide the corresponding detail, stress category		
	and example from table 11.9.3.1-1.		
Subsection:	835.07.02 Mast Arm Poles.		
Revision:	Replace the second sentence of the fourth paragraph with the following: The detailed analysis		
	shall be certified by a Professional Engineer licensed in the Commonwealth of Kentucky.		
Subsection:	· · · · · · · · · · · · · · · · · · ·		
Revision:	Replace number 7) after the fourth paragraph with the following: 7) Fatigue calculations should		
	be shown for all fatigue related connections. Provide the corresponding detail, stress category		
	and example from table 11.9.3.1-1.		
Subsection:	835.07.03 Anchor Bolts.		
Revision:	Add the following to the end of the paragraph: There shall be two steel templates (one can be		
	used for the headed part of the anchor bolt when designed in this manner) provided per pole.		
	Templates shall be contained within a 26.5 inch diameter. All templates shall be fully galvanized		
	(ASTM A 153).		
	835.16.05 Optical Units.		
Revision:	Replace the 3rd paragraph with the following:		
	The list of certified products can be found on the following website: http://www.intertek.com.		
	835.19.01 Pedestrian Detector Body.		
Revision:	Replace the first sentence with the following: Provide a four holed pole mounted aluminum		
	rectangular housing that is compatible with the pedestrian detector.		
	843.01.01 Geotextile Fabric.		
Table:	TYPE I FABRIC GEOTEXTILES FOR SLOPE PROTECTION AND CHANNEL LINING		
Revision:	Add the following to the chart:		
	Property Minimum Value ⁽¹⁾ Test Method		
	CBR Puncture (lbs) 494 ASTM D6241		
	Permittivity (1/s) 0.7 ASTM D4491		


Contract ID: 153225 Page 67 of 97

Subsection:	843.01.01 Geotextile Fabric	C.	
Table:	TYPE II FABRIC GEOTEXTILES FOR UNDERDRAINS		
Revision:	Add the following to the chart:		
	Property Property	Minimum Value ⁽¹⁾	Test Method
	CBR Puncture (lbs)	210	ASTM D6241
	Permittivity (1/s)	0.5	ASTM D4491
Subsection:	843.01.01 Geotextile Fabric	с.	
	TYPE III FABRIC GEOTEXTILES FOR SUBGRADE OR EMBANKMENT STABILIZATION		
Revision:	Add the following to the chart:		
	<u>Property</u>	Minimum Value ⁽¹⁾	Test Method
	CBR Puncture (lbs)	370	ASTM D6241
	Permittivity (1/s)	0.05	ASTM D4491
Subsection:	843.01.01 Geotextile Fabric	с.	
	TYPE IV FABRIC GEOTEXTILES FOR EMBANKMENT DRAINAGE BLANKETS AND		
	PAVEMENT EDGE DRAI		
Revision:	Add the following to the chart:		
	<u>Property</u>	Minimum Value ⁽¹⁾	Test Method
	CBR Puncture (lbs)	309	ASTM D6241
	Permittivity (1/s)	0.5	ASTM D4491
Subsection:	843.01.01 Geotextile Fabric	c.	
Table:	TYPE V HIGH STRENGT	H GEOTEXTILE FABRIC	
Revision:	Make the following changes to the chart:		
	<u>Property</u>	Minimum Value ⁽¹⁾	Test Method
	CBR Puncture (lbs)	618	ASTM D6241
].	Apparent Opening Size	U.S. #40 ⁽³⁾	ASTM D4751
	(3) Maximum average roll value.		
1			

2012 STANDARD DRAWINGS THAT APPLY

TYPICAL GUARDRAIL INSTALLATIONS	RBI-001-10
TYPICAL GUARDRAIL INSTALLATIONS	RBI-002-06
INSTALLATION OF GUARDRAIL END TREATMENT TYPE 1	RBI-004-04
GUARDRAIL TERMINAL SECTIONS	RBR-010-05
GUARDRAIL END TREATMENT TYPE 1	RBR-020-05
TEMPORARY SILT FENCE	RDX-210-02
TEMPORARY SILT FENCE WITH WOVEN WIRE FENCE FABRIC	RDX-215
SILT TRAP - TYPE A	
SILT TRAP - TYPE C	RDX-230
CURVE WIDENING AND SUPERELEVATION TRANSITIONS	
SUPERELEVATION FOR MULTILANE PAVEMENTS	RGS-002-05
MISCELLANEOUS STANDARDS PART 1	RGX-001-05
APPROACHES, ENTRANCES, AND MAIL BOX TURNOUT	
NETTING	RRE-002-04
SHOULDER CLOSURE	
POST SPLICING DETAIL	TTD-110-01
PAVEMENT CONDITION WARNING SIGNS	TTD-125-01
MOBILE OPERATION FOR PAINT STRIPING CASE I	TTS-100-01
MOBILE OPERATION FOR PAINT STRIPING CASE II	TTS-105-01





ITEM NO.

SHEET NO.

LIN. FT.

GUARDRAIL-STEEL W BEAM-DOUBLE FACE - LIN. FT.

THE RAIL ELEMENT SHALL COMPLY WITH AASHTO M-180-CLASS A. TYPE II.

ALL LAPS SHALL BE PLACED IN THE DIRECTION OF TRAFFIC

② 8 - 5%"× 11/4" LONG BUTTON HEAD BOLTS AND HEX HEAD RECESS NUTS REQUIRED FOR EACH RAIL SPLICE.

 $56^{\prime\prime\prime}$ ×8" BUTTON HEAD BOLT, HEX HEAD RECESS NUT AND ONE $56^{\prime\prime\prime}$ ROUND WASHER (TYP.). BOLT SHALL HAVE A MINIMUM THREAD LENGTH OF 2".

BOTH 12'-6' AND 25' LENGTHS OF "W" BEAM GUARDRAIL SECTIONS WILL BE PERMITTED UNLESS OTHERWISE DIRECTED BY THE ENGINEER.


GUARDRAIL "W" BEAM


DIVISION OF DESIGN

12-11-12 DATE

100

KENTUCKY





PART III

EMPLOYMENT, WAGE AND RECORD REQUIREMENTS

WEBSTER COUNTY 117GR15R065-CB06

TRANSPORTATION CABINET DEPARTMENT OF HIGHWAYS

LABOR AND WAGE REQUIREMENTS APPLICABLE TO OTHER THAN FEDERAL-AID SYSTEM PROJECTS

- I. Application
- II. Nondiscrimination of Employees (KRS 344)
- III. Payment of Predetermined Minimum Wages
- IV. Statements and Payrolls

I. APPLICATION

- 1. These contract provisions shall apply to all work performed on the contract by the contractor with his own organization and with the assistance of workmen under his immediate superintendence and to all work performed on the contract by piecework, station work or by subcontract. The contractor's organization shall be construed to include only workmen employed and paid directly by the contractor and equipment owned or rented by him, with or without operators.
- 2. The contractor shall insert in each of his subcontracts all of the stipulations contained in these Required Provisions and such other stipulations as may be required.
- 3. A breach of any of the stipulations contained in these Required Provisions may be grounds for termination of the contract.

II. NONDISCRIMINATION OF EMPLOYEES

AN ACT OF THE KENTUCKY GENERAL ASSEMBLY TO PREVENT DISCRIMINATION IN EMPLOYMENT KRS CHAPTER 344 EFFECTIVE JUNE 16, 1972

The contract on this project, in accordance with KRS Chapter 344, provides that during the performance of this contract, the contractor agrees as follows:

- 1. The contractor shall not fail or refuse to hire, or shall not discharge any individual, or otherwise discriminate against an individual with respect to his compensation, terms, conditions, or privileges of employment, because of such individual's race, color, religion, national origin, sex, disability or age (between forty and seventy); or limit, segregate, or classify his employees in any way which would deprive or tend to deprive an individual of employment opportunities or otherwise adversely affect his status as an employee, because of such individual's race, color, religion, national origin, sex, disability or age (between forty and seventy). The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- 2. The contractor shall not print or publish or cause to be printed or published a notice or advertisement relating to employment by such an employer or membership in or any classification or referral for employment by the employment agency, indicating any preference, limitation, specification, or discrimination, based on race, color, religion, national origin, sex, disability or age (between forty and seventy), except that such notice or advertisement may indicate a preference, limitation, or specification based on religion, or national origin when religion, or national origin is a bona fide occupational qualification for employment.
- 3. If the contractor is in control of apprenticeship or other training or retraining, including on-the-job training programs, he shall not discriminate against an individual

because of his race, color, religion, national origin, sex, disability or age (between forty and seventy), in admission to, or employment in any program established to provide apprenticeship or other training.

4. The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representative of the contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment. The contractor will take such action with respect to any subcontract or purchase order as the administrating agency may direct as a means of enforcing such provisions, including sanctions for non-compliance.

III. PAYMENT OF PREDETERMINED MINIMUM WAGES

- 1. These special provisions are supplemented elsewhere in the contract by special provisions which set forth certain predetermined minimum wage rates. The contractor shall pay not less than those rates.
- 2. The minimum wage determination schedule shall be posted by the contractor, in a manner prescribed by the Department of Highways, at the site of the work in prominent places where it can be easily seen by the workers.

IV. STATEMENTS AND PAYROLLS

- 1. All contractors and subcontractors affected by the terms of KRS 337.505 to 337.550 shall keep full and accurate payroll records covering all disbursements of wages to their employees to whom they are required to pay not less than the prevailing rate of wages. Payrolls and basic records relating thereto will be maintained during the course of the work and preserved for a period of one (1) year from the date of completion of this contract.
- 2. The payroll records shall contain the name, address and social security number of each employee, his correct classification, rate of pay, daily and weekly number of hours worked, itemized deductions made and actual wages paid.
- 3. The contractor shall make his daily records available at the project site for inspection by the State Department of Highways contracting office or his authorized representative.

Periodic investigations shall be conducted as required to assure compliance with the labor provisions of the contract. Interrogation of employees and officials of the contractor shall be permitted during working hours.

Aggrieved workers, Highway Managers, Assistant District Engineers, Resident Engineers and Project Engineers shall report all complaints and violations to the Division of Contract Procurement.

The contractor shall be notified in writing of apparent violations. The contractor may correct the reported violations and notify the Department of Highways of the action taken or may request an informal hearing. The request for hearing shall be in writing within ten (10) days after receipt of the notice of the reported violation. The contractor may submit

records and information which will aid in determining the true facts relating to the reported violations.

Any person or organization aggrieved by the action taken or the findings established as a result of an informal hearing by the Division of Contract Procurement may request a formal hearing.

- 4. The wages of labor shall be paid in legal tender of the United States, except that this condition will be considered satisfied if payment is made by a negotiable check, on a solvent bank, which may be cashed readily by the employee in the local community for the full amount, without discount or collection charges of any kind. Where checks are used for payments, the contractor shall make all necessary arrangements for them to be cashed and shall give information regarding such arrangements.
- 5. No fee of any kind shall be asked or accepted by the contractor or any of his agents from any person as a condition of employment on the project.
- 6. No laborers shall be charged for any tools used in performing their respective duties except for reasonably avoidable loss or damage thereto.
- 7. Every employee on the work covered by this contract shall be permitted to lodge, board, and trade where and with whom he elects and neither the contractor nor his agents, nor his employees shall directly or indirectly require as a condition of employment that an employee shall lodge, board or trade at a particular place or with a particular person.
- 8. Every employee on the project covered by this contract shall be an employee of either the prime contractor or an approved subcontractor.
- 9. No charge shall be made for any transportation furnished by the contractor or his agents to any person employed on the work.
- 10. No individual shall be employed as a laborer or mechanic on this contract except on a wage basis, but this shall not be construed to prohibit the rental of teams, trucks or other equipment from individuals.

No Covered employee may be employed on the work except in accordance with the classification set forth in the schedule mentioned above; provided, however, that in the event additional classifications are required, application shall be made by the contractor to the Department of Highways and (1) the Department shall request appropriate classifications and rates from the proper agency, or (2) if there is urgent need for additional classification to avoid undue delay in the work, the contractor may employ such workmen at rates deemed comparable to rates established for similar classifications provided he has made written application through the Department of Highways, addressed to the proper agency, for the supplemental rates. The contractor shall retroactively adjust, upon receipt of the supplemental rates schedule, the wages of any employee paid less than the established rate and may adjust the wages of any employee overpaid.

- 11. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any laborer or mechanic in any work-week in which he is employed on such work, to work in excess of eight hours in any calendar day or in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one half times his basic rate of pay for all hours worked in excess of eight hours in any calendar day or in excess of forty hours in such work-week. A laborer, workman or mechanic and an employer may enter into a written agreement or a collective bargaining agreement to work more than eight (8) hours a calendar day but not more than ten (10) hours a calendar day for the straight time hourly rate. This agreement shall be in writing and shall be executed prior to the employee working in excess of eight (8) hours, but not more than ten (10) hours, in any one (1) calendar day.
- 12. Payments to the contractor may be suspended or withheld due to failure of the contractor to pay any laborer or

mechanic employed or working on the site of the work, all or part of the wages required under the terms of the contract. The Department may suspend or withhold payments only after the contractor has been given written notice of the alleged violation and the contractor has failed to comply with the wage determination of the Department of Highways.

13. Contractors and subcontractors shall comply with the sections of Kentucky Revised Statutes, Chapter 337 relating to contracts for Public Works.

Revised 2-16-95

WEBSTER COUNTY 117GR15R065-CB06 Contract ID: 153225 Page 77 of 97

EXECUTIVE BRANCH CODE OF ETHICS

In the 1992 regular legislative session, the General Assembly passed and Governor Brereton Jones signed Senate Bill 63 (codified as KRS 11A), the Executive Branch Code of Ethics, which states, in part:

KRS 11A.040 (6) provides:

No present or former public servant shall, within six (6) months of following termination of his office or employment, accept employment, compensation or other economic benefit from any person or business that contracts or does business with the state in matters in which he was directly involved during his tenure. This provision shall not prohibit an individual from returning to the same business, firm, occupation, or profession in which he was involved prior to taking office or beginning his term of employment, provided that, for a period of six (6) months, he personally refrains from working on any matter in which he was directly involved in state government. This subsection shall not prohibit the performance of ministerial functions, including, but not limited to, filing tax returns, filing applications for permits or licenses, or filing incorporation papers.

KRS 11A.040 (8) states:

A former public servant shall not represent a person in a matter before a state agency in which the former public servant was directly involved, for a period of one (1) year after the latter of:

- a) The date of leaving office or termination of employment; or
- b) The date the term of office expires to which the public servant was elected.

This law is intended to promote public confidence in the integrity of state government and to declare as public policy the idea that state employees should view their work as a public trust and not as a way to obtain private benefits.

If you have worked for the executive branch of state government within the past six months, you may be subject to the law's prohibitions. The law's applicability may be different if you hold elected office or are contemplating representation of another before a state agency.

Also, if you are affiliated with a firm which does business with the state and which employs former state executive-branch employees, you should be aware that the law may apply to them.

In case of doubt, the law permits you to request an advisory opinion from the Executive Branch Ethics Commission, Room 136, Capitol Building, 700 Capitol Avenue, Frankfort, Kentucky 40601; telephone (502) 564-7954.

Kentucky Equal Employment Opportunity Act of 1978

The requirements of the Kentucky Equal Employment Opportunity Act of 1978 (KRS 45.560-45.640) shall apply to this Contract. The apparent low Bidder will be required to submit EEO forms to the Division of Construction Procurement, which will then forward to the Finance and Administration Cabinet for review and approval. No award will become effective until all forms are submitted and EEO/CC has certified compliance. The required EEO forms are as follows:

- EEO-1: Employer Information Report
- Affidavit of Intent to Comply
- Employee Data Sheet
- Subcontractor Report

These forms are available on the Finance and Administration's web page under *Vendor Information*, *Standard Attachments and General Terms* at the following address: https://www.eProcurement.ky.gov.

Bidders currently certified as being in compliance by the Finance and Administration Cabinet may submit a copy of their approval letter in lieu of the referenced EEO forms.

For questions or assistance please contact the Finance and Administration Cabinet by email at **finance.contractcompliance@ky.gov** or by phone at 502-564-2874.

General Decision Number: KY150102 09/04/2015 KY102

Superseded General Decision Number: KY20140102

State: Kentucky

Construction Type: Highway

Counties: Allen, Ballard, Butler, Caldwell, Calloway, Carlisle, Christian, Crittenden, Daviess, Edmonson, Fulton, Graves, Hancock, Henderson, Hickman, Hopkins, Livingston, Logan, Lyon, Marshall, McCracken, McLean, Muhlenberg, Ohio, Simpson, Todd, Trigg, Union, Warren and Webster Counties in Kentucky.

HIGHWAY CONSTRUCTION PROJECTS (excluding tunnels, building structures in rest area projects & railroad construction; bascule, suspension & spandrel arch bridges designed for commercial navigation, bridges involving marine construction; and other major bridges).

Note: Executive Order (EO) 13658 establishes an hourly minimum wage of \$10.10 for 2015 that applies to all contracts subject to the Davis-Bacon Act for which the solicitation is issued on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.10 (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract. The EO minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification N	umbor	Publication	Dato
	umber		Date
0		01/02/2015	
1		01/30/2015	
2		02/20/2015	
3		02/27/2015	
4		03/06/2015	
5		03/20/2015	
6		03/27/2015	
7		05/01/2015	
8		05/08/2015	
9		05/22/2015	
10		05/29/2015	
11		06/05/2015	
12		06/12/2015	
13		06/19/2015	
14		08/21/2015	
15		09/04/2015	

^{*} BRIN0004-002 06/01/2015

BALLARD, BUTLER, CALDWELL, CARLISLE, CRITTENDEN, DAVIESS, EDMONSON, FULTON, GRAVES, HANCOCK, HENDERSON, HICKMAN, HOPKINS, LIVINGSTON, LYON, MARSHALL, MCCRACKEN, MCLEAN, MUHLENBERG, OHIO, UNION, and WEBSTER COUNTIES

	Rates	Fringes
BRICKLAYER Ballard, Caldwell, Carlisle, Crittenden, Fulton, Graves, Hickman, Livingston, Lyon,		
Marshall, and McCracken Counties Butler, Edmonson, Hopkins, Muhlenberg, and Ohio	\$ 29.52	13.37
Counties	\$ 25.96	10.64
Henderson, McLean, Union, and Webster Counties	.\$ 28.68	13.72
* BRTN0004-005 06/01/2015		
ALLEN, CALLOWAY, CHRISTIAN, LOGAN WARREN COUNTIES	N, SIMPSON, TODE	, TRIGG, and
	Rates	Fringes
BRICKLAYER	\$ 25.96	10.64
CARP0357-002 05/01/2015		
	Rates	Fringes
CARPENTER	\$ 41.63	16.02 16.02 16.02
	JADDEN COIMETEC.	
BUTLER, EDMONSON, LOGAN, TODD & V		
	Rates	Fringes
ELECTRICIAN	.\$ 30.01 	15.65
ELEC0429-001 06/01/2014		
ALLEN & SIMPSON COUNTIES:		
	Rates	Fringes
ELECTRICIAN	.\$ 24.44 1	0.15 + 5%
ELEC0816-002 06/01/2015		
BALLARD, CALDWELL, CALLOWAY, CARI FULTON (Except a 5 mile radius of HICKMAN, LIVINGSTON, LYON, MARSHA	City Hall in F	ulton), GRAVES,

Rates Fringes

ELECTRICIAN.....\$ 31.03 25.5%+6.35

Cable spicers receive \$.25 per hour additional.

ELEC1701-003 01/01/2015

DAVIESS, HANCOCK, HENDERSON, HOPKINS, MCLEAN, MUHLENBERG, OHIO, UNION & WEBSTER COUNTIES:

	Rates	Fringes
ELECTRICIAN	\$ 30.15	14.69

Cable spicers receive \$.25 per hour additional.

ELEC1925-002 01/01/2015

FULTON COUNTY (Up to a 5 mile radius of City Hall in Fulton):

	Rates	Fringes
CABLE SPLICER		10.27
ELECTRICIAN	\$ 24.55	11.51

ENGI0181-017 07/01/2015

	Rates	Fringes
POWER EQUIPMENT OPERATOR		
GROUP 1\$	29.95	14.40
GROUP 2\$	27.26	14.40
GROUP 3\$	27.68	14.40
GROUP 4\$	26.96	14.40

OPERATING ENGINEER CLASSIFICATIONS

GROUP 1 - A-Frame Winch Truck; Auto Patrol; Backfiller; Batcher Plant; Bituminous Paver; Bituminous Transfer Machine; Boom Cat; Bulldozer; Mechanic; Cableway; Carry-All Scoop; Carry Deck Crane; Central Compressor Plant; Cherry Picker; Clamshell; Concrete Mixer (21 cu. ft. or Over); Concrete Paver; Truck-Mounted Concrete Pump; Core Drill; Crane; Crusher Plant; Derrick; Derrick Boat; Ditching & Trenching Machine; Dragline; Dredge Operator; Dredge Engineer; Elevating Grader & Loaders; Grade-All; Gurries; Heavy Equipment Robotics Operator/Mechanic; High Lift; Hoe-Type Machine; Hoist (Two or More Drums); Hoisting Engine (Two or More Drums); Horizontal Directional Drill Operator; Hydrocrane; Hyster; KeCal Loader; LeTourneau; Locomotive; Mechanic; Mechanically Operated Laser Screed; Mechanic Welder; Mucking Machine; Motor Scraper; Orangepeel Bucket; Overhead Crane; Piledriver; Power Blade; Pumpcrete; Push Dozer; Rock Spreader, attached to equipment; Rotary Drill; Roller (Bituminous); Rough Terrain Crane; Scarifier; Scoopmobile; Shovel; Side Boom; Subgrader; Tailboom; Telescoping Type Forklift; Tow or Push Boat; Tower Crane (French, German & other types); Tractor Shovel; Truck Crane; Tunnel Mining Machines, including Moles, Shields or

similar types of Tunnel Mining Equipment

GROUP 2 - Air Compressor (Over 900 cu. ft. per min.);
Bituminous Mixer; Boom Type Tamping Machine; Bull Float;
Concrete Mixer (Under 21 cu. ft.); Dredge Engineer;
Electric Vibrator; Compactor/Self-Propelled Compactor;
Elevator (One Drum or Buck Hoist); Elevator (When used to Hoist Building Material); Finish Machine; Firemen & Hoist (One Drum); Flexplane; Forklift (Regardless of Lift Height); Form Grader; Joint Sealing Machine; Outboard Motor Boat; Power Sweeper (Riding Type); Roller (Rock); Ross Carrier; Skid Mounted or Trailer Mounted Conrete Pump; Skid Steer Machine with all Attachments; Switchman or Brakeman; Throttle Valve Person; Tractair & Road Widening Trencher; Tractor (50 H.P. or Over); Truck Crane Oiler; Tugger; Welding Machine; Well Points; & Whirley Oiler

GROUP 3 -All Off Road Material Handling Equipment, including Articulating Dump Trucks; Greaser on Grease Facilities servicing Heavy Equipment

GROUP 4 - Bituminous Distributor; Burlap & Curing Machine; Cement Gun; Concrete Saw; Conveyor; Deckhand Oiler; Grout Pump; Hydraulic Post Driver; Hydro Seeder; Mud Jack; Oiler; Paving Joint Machine; Power Form Handling Equipment; Pump; Roller (Earth); Steerman; Tamping Machine; Tractor (Under 50 H.P.); & Vibrator

CRANES - with booms 150 ft. & Over (Including JIB), and where the length of the boom in combination with the length of the piling equals or exceeds 150 ft. - \$1.00 above Group 1 rate

EMPLOYEES ASSIGNED TO WORK BELOW GROUND LEVEL ARE TO BE PAID 10% ABOVE BASIC WAGE RATE. THIS DOES NOT APPLY TO OPEN CUT WORK.

IRON0070-005 06/01/2015

BUTLER COUNTY (Eastern eighth, including the Townships of Decker, Lee & Tilford);
EDMONSON COUNTY (Northern three-fourths, including the Townships of Asphalt, Bee Spring, Brownsville, Grassland, Huff, Kyrock, Lindseyville, Mammoth Cave, Ollie, Prosperity, Rhoda, Sunfish & Sweden)

Rates Fringes

IRONWORKER

Structural; Ornamental; Reinforcing; Precast

Concrete Erectors......\$ 27.56 20.30

IRON0103-004 08/01/2015

DAVIESS, HANCOCK, HENDERSON, HOPKINS, MCLEAN, OHIO, UNION & WEBSTER COUNTIES
BUTLER COUNTY (Townships of Aberdeen, Bancock, Casey,

Dexterville, Dunbar, Elfie, Gilstrap, Huntsville, Logansport, Monford, Morgantown, Provo, Rochester, South Hill & Welchs Creek);

CALDWELL COUNTY (Northeastern third, including the Township of Creswell);

CHRISTIAN COUNTY (Northern third, including the Townships of Apex, Crofton, Kelly, Mannington & Wynns);
CRITTENDEN COUNTY (Northeastern half, including the Townships of Grove, Mattoon, Repton, Shady Grove & Tribune);
MUHLENBERG COUNTY (Townships of Bavier, Beech Creek Junction, Benton, Brennen, Browder, Central City, Cleaton, Depoy, Drakesboro, Eunis, Graham, Hillside, Luzerne, Lynn City, Martwick, McNary, Millport, Moorman, Nelson, Paradise,

Rates Fringes

Ironworkers:.....\$ 28.14 18.675

Powderly, South Carrollton, Tarina & Weir)

IRON0492-003 05/01/2014

ALLEN, LOGAN, SIMPSON, TODD & WARREN COUNTIES
BUTLER COUNTY (Southern third, including the Townships of
Boston, Berrys Lick, Dimple, Jetson, Quality, Sharer, Sugar
Grove & Woodbury);

CHRISTIAN COUNTY (Eastern two-thirds, including the Townships of Bennettstown, Casky, Herndon, Hopkinsville, Howell, Masonville, Pembroke & Thompsonville);

EDMONSON COUNTY (Southern fourth, including the Townships of Chalybeate & Rocky Hill);

MUHLENBERG COUNTY (Southern eighth, including the Townships of Dunnior, Penrod & Rosewood)

Rates Fringes

Ironworkers:.....\$ 24.33

IRON0782-006 05/01/2014

BALLARD, CALLOWAY, CARLISLE, FULTON, GRAVES, HICKMAN, LIVINGSTON, LYON, MARSHALL, MCCRACKEN & TRIGG COUNTIES CALDWELL COUNTY (Southwestern two-thirds, including the Townships of Cedar Bluff, Cider, Claxton, Cobb, Crowtown, Dulaney, Farmersville, Fredonia, McGowan, Otter Pond & Princeton);

CHRISTIAN COUNTY (Western third, Excluding the Townships of Apex, Crofton, Kelly, Mannington, Wynns, Bennettstown, Casky, Herndon, Hopkinsville, Howell, Masonville, Pembroke & Thompsonville);

CRITTENDEN COUNTY (Southwestern half, including the Townships of Crayne, Dycusburg, Frances, Marion, Mexico, Midway, Sheridan & Told)

Rates Fringes

Ironworkers:

Projects with a total

contract cos	of		
\$20,000,000.	00 or above\$	27.09	20.66
All Other Wo	rk\$	25.50	19.02

LABO0189-005 07/01/2014

BALLARD, CALLOWAY, CARLISLE, FULTON, GRAVES, HICKMAN, LIVINGSTON, LYON, MARSHALL & MCCRACKEN COUNTIES

	I	Rates	Fringes
Laborers:			
GROUP	1\$	21.50	12.26
GROUP	2\$	21.75	12.26
GROUP	3\$	21.80	12.26
GROUP	4\$	22.40	12.26

LABORER CLASSIFICATIONS

GROUP 1 - Aging & Curing of Concrete; Asbestos Abatement Worker; Asphalt Plant; Asphalt; Batch Truck Dump; Carpenter Tender; Cement Mason Tender; Cleaning of Machines; Concrete; Demolition; Dredging; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Level D; Flagperson; Grade Checker; Hand Digging & Hand Back Filling; Highway Marker Placer; Landscaping, Mesh Handler & Placer; Puddler; Railroad; Rip-rap & Grouter; Right-of-Way; Sign, Guard Rail & Fence Installer; Signal Person; Sound Barrier Installer; Storm & Sanitary Sewer; Swamper; Truck Spotter & Dumper; Wrecking of Concrete Forms; General Cleanup

GROUP 2 - Batter Board Man (Sanitary & Storm Sewer);
Brickmason Tender; Mortar Mixer Operator; Scaffold Builder;
Burner & Welder; Bushammer; Chain Saw Operator; Concrete
Saw Operator; Deckhand Scow Man; Dry Cement Handler;
Environmental - Nuclear, Radiation, Toxic & Hazardous Waste
- Level C; Forklift Operator for Masonary; Form Setter;
Green Concrete Cutting; Hand Operated Grouter & Grinder
Machine Operator; Jackhammer; Pavement Breaker; Paving
Joint Machine; Pipelayer; Plastic Pipe Fusion; Power Driven
Georgia Buggy & Wheel Barrow; Power Post Hole Digger;
Precast Manhole Setter; Walk-Behind Tamper; Walk-Behind
Trencher; Sand Blaster; Concrete Chipper; Surface
Grinder; Vibrator Operator; Wagon Driller

GROUP 3 - Asphalt Luteman & Raker; Gunnite Nozzleman; Gunnite Operator & Mixer; Grout Pump Operator; Blaster; Side Rail Setter; Rail Paved Ditches; Screw Operator; Tunnel (Free Air); Water Blaster

GROUP 4 - Caisson Worker (Free Air); Cement Finisher; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Levels A & B; Miner & Driller (Free Air); Tunnel Blaster; & Tunnel Mucker (Free Air); Directional & Horizontal Boring; Air Track Drillers (All Types); Powdermen & Blasters; Troxler & Concrete Tester if Laborer is Utilized

LABO0189-006 07/01/2014

ALLEN, BUTLER, CALDWELL, CHRISTIAN, DAVIESS, EDMONSON, HANCOCK, HOPKINS, LOGAN, MCLEAN, MUHLENBERG, OHIO, SIMPSON, TODD, TRIGG & WARREN COUNTIES

	I	Rates	Fringes
			_
Laborers:			
GROUP	1\$	22.66	11.10
GROUP	2\$	22.91	11.10
GROUP	3\$	22.96	11.10
GROUP	4\$	23.56	11.10

LABORER CLASSIFICATIONS

GROUP 1 - Aging & Curing of Concrete; Asbestos Abatement Worker; Asphalt Plant; Asphalt; Batch Truck Dump; Carpenter Tender; Cement Mason Tender; Cleaning of Machines; Concrete; Demolition; Dredging; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Level D; Flagperson; Grade Checker; Hand Digging & Hand Back Filling; Highway Marker Placer; Landscaping, Mesh Handler & Placer; Puddler; Railroad; Rip-rap & Grouter; Right-of-Way; Sign, Guard Rail & Fence Installer; Signal Person; Sound Barrier Installer; Storm & Sanitary Sewer; Swamper; Truck Spotter & Dumper; Wrecking of Concrete Forms; General Cleanup

GROUP 2 - Batter Board Man (Sanitary & Storm Sewer);
Brickmason Tender; Mortar Mixer Operator; Scaffold Builder;
Burner & Welder; Bushammer; Chain Saw Operator; Concrete
Saw Operator; Deckhand Scow Man; Dry Cement Handler;
Environmental - Nuclear, Radiation, Toxic & Hazardous Waste
- Level C; Forklift Operator for Masonary; Form Setter;
Green Concrete Cutting; Hand Operated Grouter & Grinder
Machine Operator; Jackhammer; Pavement Breaker; Paving
Joint Machine; Pipelayer; Plastic Pipe Fusion; Power Driven
Georgia Buggy & Wheel Barrow; Power Post Hole Digger;
Precast Manhole Setter; Walk-Behind Tamper; Walk-Behind
Trencher; Sand Blaster; Concrete Chipper; Surface
Grinder; Vibrator Operator; Wagon Driller

GROUP 3 - Asphalt Luteman & Raker; Gunnite Nozzleman; Gunnite Operator & Mixer; Grout Pump Operator; Blaster; Side Rail Setter; Rail Paved Ditches; Screw Operator; Tunnel (Free Air); Water Blaster

GROUP 4 - Caisson Worker (Free Air); Cement Finisher; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Levels A & B; Miner & Driller (Free Air); Tunnel Blaster; & Tunnel Mucker (Free Air); Directional & Horizontal Boring; Air Track Drillers (All Types); Powdermen & Blasters; Troxler & Concrete Tester if Laborer is Utilized

LABO0561-001 07/01/2014

CRITTENDEN, HENDERSON, UNION & WEBSTER COUNTIES

Rates Fringes

Laborers:

GROUP 1	\$ 21.36	12.65
GROUP 2	\$ 21.61	12.65
GROUP 3	\$ 21.66	12.65
GROUP 4	\$ 22.26	12.65

LABORER CLASSIFICATIONS

GROUP 1 - Aging & Curing of Concrete; Asbestos Abatement Worker; Asphalt Plant; Asphalt; Batch Truck Dump; Carpenter Tender; Cement Mason Tender; Cleaning of Machines; Concrete; Demolition; Dredging; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Level D; Flagperson; Grade Checker; Hand Digging & Hand Back Filling; Highway Marker Placer; Landscaping, Mesh Handler & Placer; Puddler; Railroad; Rip-rap & Grouter; Right-of-Way; Sign, Guard Rail & Fence Installer; Signal Person; Sound Barrier Installer; Storm & Sanitary Sewer; Swamper; Truck Spotter & Dumper; Wrecking of Concrete Forms; General Cleanup

GROUP 2 - Batter Board Man (Sanitary & Storm Sewer);
Brickmason Tender; Mortar Mixer Operator; Scaffold Builder;
Burner & Welder; Bushammer; Chain Saw Operator; Concrete
Saw Operator; Deckhand Scow Man; Dry Cement Handler;
Environmental - Nuclear, Radiation, Toxic & Hazardous Waste
- Level C; Forklift Operator for Masonary; Form Setter;
Green Concrete Cutting; Hand Operated Grouter & Grinder
Machine Operator; Jackhammer; Pavement Breaker; Paving
Joint Machine; Pipelayer; Plastic Pipe Fusion; Power Driven
Georgia Buggy & Wheel Barrow; Power Post Hole Digger;
Precast Manhole Setter; Walk-Behind Tamper; Walk-Behind
Trencher; Sand Blaster; Concrete Chipper; Surface
Grinder; Vibrator Operator; Wagon Driller

GROUP 3 - Asphalt Luteman & Raker; Gunnite Nozzleman; Gunnite Operator & Mixer; Grout Pump Operator; Blaster; Side Rail Setter; Rail Paved Ditches; Screw Operator; Tunnel (Free Air); Water Blaster

GROUP 4 - Caisson Worker (Free Air); Cement Finisher; Environmental - Nuclear, Radiation, Toxic & Hazardous Waste - Levels A & B; Miner & Driller (Free Air); Tunnel Blaster; & Tunnel Mucker (Free Air); Directional & Horizontal Boring; Air Track Drillers (All Types); Powdermen & Blasters; Troxler & Concrete Tester if Laborer is Utilized

PAIN0032-002 05/01/2015

BALLARD COUNTY

I	Rates	Fringes
Painters:		
Bridges\$	32.56	15.18
All Other Work\$	30.26	15.18

Spray, Blast, Steam, High & Hazardous (Including Lead Abatement) and All Epoxy - \$1.00 Premium

PAIN0118-003 06/01/2014

EDMONSON COUNTY:

	Rates	Fringes	
Painters:	ć 10 F0	11 07	
Brush & Roller Spray, Sandblast, Power Tools, Waterblast & Steam	\$ 18.50	11.97	
Cleaning	\$ 19.50	11.97	

PAIN0156-006 04/01/2015

DAVIESS, HANCOCK, HENDERSON, MCLEAN, OHIO, UNION & WEBSTER COUNTIES

	F	Rates	Fringes
Painters:			
BRIDGES			
GROUP 1.		27.60	12.85
GROUP 2.		27.85	12.85
GROUP 3.		28.60	12.85
GROUP 4.		29.60	12.85
ALL OTHER	R WORK:		
GROUP 1.		26.45	12.85
GROUP 2.		26.70	12.85
GROUP 3.		27.45	12.85
GROUP 4.	\$	28.45	12.85

PAINTER CLASSIFICATIONS

GROUP 1 - Brush & Roller

GROUP 2 - Plasterers

GROUP 3 - Spray; Sandblast; Power Tools; Waterblast; Steamcleaning; Brush & Roller of Mastics, Creosotes, Kwinch Koate & Coal Tar Epoxy

GROUP 4 - Spray of Mastics, Creosotes, Kwinch Koate & Coal Tar Epoxy

PAIN0456-003 01/01/2015

ALLEN, BUTLER, LOGAN, MUHLENBERG, SIMPSON, TODD & WARREN COUNTIES:

	Rates	Fringes
Painters:		
BRIDGES		
Brush & Roller	.\$ 23.25	9.95
Spray; Sandblast; Power		

Tools; Waterblast & Steam		
Cleaning\$	24.25	9.95
ALL OTHER WORK		
Brush & Roller\$	19.25	9.95
Spray; Sandblast; Power		
Tools; Waterblast & Steam		
Cleaning\$	20.25	9.95

ALL OTHER WORK - HIGH TIME PAY Over 35 feet (up to 100 feet) - \$1.00 above base wage 100 feet and over - \$2.00 above base wage

DURING SPRAY PAINTING AND SANDBLASTING OPERATIONS, POT TENDERS SHALL RECEIVE THE SAME WAGE RATES AS THE SPRAY PAINTER OR NOZZLE OPERATOR

PAIN0500-002 06/01/2015

CALDWELL, CALLOWAY, CARLISLE, CHRISTIAN, CRITTENDEN, FULTON, GRAVES, HICKMAN, HOPKINS, LIVINGSTON, LYON, MARSHALL, MCCRACKEN & TRIGG COUNTIES:

	Rates	Fringes
Painters:		
Bridges	\$ 26.85	12.35
All Other Work	\$ 20.60	12.35
Waterblasting units with 3500		· <u>+</u>

Spraypainting and all abrasive blasting - \$1.00 premium Work 40 ft. and above ground level - \$1.00 premium

PLUM0184-002 07/01/2013

BALLARD, CALDWELL, CALLOWAY, CARLISLE, CHRISTIAN, CRITTENDEN, FULTON, GRAVES, HICKMAN, LIVINGSTON, LYON, MARSHALL, MCCRACKEN and TRIGG COUNTIES

		Rates	Fringes
Plumber;	Steamfitter	\$ 33.11	14.83
PLUM050	2-004 08/01/2013		

ALLEN, BUTLER, EDMONSON, SIMPSON & WARREN

		Rates	Fringes
Plumber;	Steamfitter	\$ 32.00	17.17
PLUM0633	3-002 08/01/2013		

DAVIESS, HANCOCK, HENDERSON, HOPKINS, LOGAN, MCLEAN, MUHLENBERG, OHIO, TODD, UNION & WEBSTER COUNTIES:

	Rates	Fringes
PLUMBER/PIPEFITTER	\$ 29.87	14.25
TEAM0089-003 03/30/2014		

ALLEN, BUTLER, EDMONSON, LOGAN, SIMPSON & WARREN COUNTIES

	Rates	Fringes
Truck drivers:		
Zone 1:		
Group 1	\$ 19.58	17.83
Group 2	\$ 19.76	17.83
Group 3		17.83
Group 4	i i	17.83

GROUP 1 - Greaser; Tire Changer

GROUP 2 - Truck Mechanic; Single Axle Dump; Flat Bed; All Terrain Vehicles when used to haul materials; Semi Trailer or Pole Trailer when used to pull building materials and equipment; Tandem Axle Dump; Driver of Distributors

GROUP 3 - Mixer All Types

GROUP 4 - Winch and A-Frame when used in transporting materials; Ross Carrier; Fork Lift when used to transport building materials; Driver on Pavement Breaker; Euclid and Other Heavy Earth Moving Equipment; Low Boy; Articulator Cat; Five Axle Vehicle

TEAM0215-003 03/31/2013

DAVIESS, HANCOCK, HENDERSON, HOPKINS, MCLEAN, MUHLENBERG, OHIO & WEBSTER COUNTIES

	Rates	Fringes
TRUCK DRIVER		
Group 1	\$ 20.93	16.85
Group 2	\$ 21.16	16.85
Group 3	\$ 21.23	16.85
Group 4	\$ 21.24	16.85

GROUP 1: Greaser, Tire Changer

GROUP 2: Truck Mechanic

GROUP 3: Single Axle Dump; Flat Bed; All Terrain Vehicle when used to haul materials; Semi Trailer or Pole Trailer when used to pull building materials and equipment; Tandem Axle Dump; Driver of Distributors; Mixer All Types

GROUP 4: Euclid and other heavy earth moving equipment; Low Boy; Articulator Cat; 5 Axle Vehicle; Winch and A- Frame when used in transporting materials; Ross Carrier; Fork Lift when used to transport building materials; Driver on

Pavement Breaker

TEAM0236-001 03/31/2013

BALLARD, CALDWELL, CALLOWAY, CARLISLE, CHRISTIAN, CRITTENDEN, FULTON, GRAVES, HICKMAN, LIVINGSTON, LYON, MARSHALL, MCCRACKEN, TODD & TRIGG COUNTIES

	Rates	Fringes
TRUCK DRIVER		
Group 1	\$ 19.38	16.85
Group 2	\$ 19.56	16.85
Group 3	\$ 19.56	16.85
Group 4	\$ 19.66	16.85
Group 5	\$ 19.64	16.85

GROUP 1: Greaser, Tire Changer

GROUP 2: Truck Mechanic

GROUP 3: Single Axle Dump; Flat Bed; All Terrain Vehicle when used to haul materials; Semi Trailer or Pole Trailer when used to pull building materials and equipment; Tandem Axle Dump; Drivers of Distributors

GROUP 4: Euclid and other heavy earth moving equipment; Low Boy; Articulator Cat; Five Axle Vehicle; Winch and A-Frame when used in transporting materials; Ross Carrier

GROUP 5: Mixer All Types

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

Fringe benefit amounts are applicable for all hours worked except when otherwise noted.

These rates are listed pursuant to the Kentucky Determination No. CR-15-I-HWY dated July 20, 2015.

No laborer, workman or mechanic shall be paid at a rate less than that of a Journeyman except those classified as bona fide apprentices.

Apprentices or trainees shall be permitted to work as such subject to Administrative Regulations adopted by the Commissioner of Workplace Standards. Copies of these regulations will be furnished upon request from any interested person.

Before using apprentices on the job the contractor shall present to the Contracting Officer written evidence of registration of such employees in a program of a State apprenticeship and training agency approved and recognized by the U. S. Bureau of Apprenticeship and Training. In the absence of such a State agency, the contractor shall submit evidence of approval and registration by the U. S. Bureau of Apprenticeship and Training.

The contractor shall submit to the Contracting Officer, written evidence of the established apprenticeship-journeyman ratios and wage rates in the project area, which will be the basis for establishing such ratios and rates for the project under the applicable contract provisions.

TO: EMPLOYERS/EMPLOYEES

PREVAILING WAGE SCHEDULE:

The wages indicated on this wage schedule are the least permitted to be paid for the occupations indicated. When an employee works in more than one classification, the employer must record the number of hours worked in each classification at the prescribed hourly base rate.

OVERTIME:

Overtime is to be paid after an employee works eight (8) hours a day or forty (40) hours a week, whichever gives the employee the greater wages. At least time and one-half the base rate is required for all overtime. A laborer, workman or mechanic and an employer may enter into a written agreement or a collective bargaining agreement to work more than eight (8) hours a calendar day but not more than ten (10) hours a calendar day for the straight time hourly rate. Wage violations or questions should be directed to the designated Engineer or the undersigned.

Director Division of Construction Procurement Frankfort, Kentucky 40622 502-564-3500

PART IV

INSURANCE

INSURANCE

The Contractor shall procure and maintain the following insurance in addition to the insurance required by law:

- 1) Commercial General Liability-Occurrence form not less than \$2,000,000 General aggregate, \$2,000,000 Products & Completed Aggregate, \$1,000,000 Personal & Advertising, \$1,000,000 each occurrence.
- 2) Automobile Liability- \$1,000,000 per accident
- 3) Employers Liability:
 - a) \$100,000 Each Accident Bodily Injury
 - b) \$500,000 Policy limit Bodily Injury by Disease
 - c) \$100,000 Each Employee Bodily Injury by Disease
- 4) The insurance required above must be evidenced by a Certificate of Insurance and this Certificate of Insurance must contain one of the following statements:
 - a) "policy contains no deductible clauses."
 - b) "policy contains _____ (amount) deductible property damage clause but company will pay claim and collect the deductible from the insured."
- 5) KENTUCKY WORKMEN'S COMPENSATION INSURANCE. The contractor shall furnish evidence of coverage of all his employees or give evidence of self-insurance by submitting a copy of a certificate issued by the Workmen's Compensation Board.

The cost of insurance is incidental to all contract items. All subcontractors must meet the same minimum insurance requirements.

PART V

BID ITEMS

153225

PROPOSAL BID ITEMS

Report Date 8/31/15

Page 1 of 1

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	220.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	146.00	TON		\$	
0030	00212		CL2 ASPH BASE 1.00D PG64-22	40.00	TON		\$	
0040	00301		CL2 ASPH SURF 0.38D PG64-22	2,135.00	TON		\$	
0050	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	5.00	EACH		\$	
0060	02014		BARRICADE-TYPE III	2.00	EACH		\$	
0070	02351		GUARDRAIL-STEEL W BEAM-S FACE	87.50	LF		\$	
080	02355		GUARDRAIL-STEEL W BEAM-S FACE A	100.00	LF		\$	
090	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		\$	
0100	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0110	02381		REMOVE GUARDRAIL	100.00	LF		\$	
0120	02562		TEMPORARY SIGNS	400.00	SQFT		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC (PAVING)	1.00	LS		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC (BRIDGE)	1.00	LS		\$	
0150	02676		MOBILIZATION FOR MILL & TEXT (PAVING)	1.00	LS		\$	
0160	02677		ASPHALT PAVE MILLING & TEXTURING	125.00	TON		\$	
0170	03240		BASE FAILURE REPAIR	92.00	SQYD		\$	
180	06510		PAVE STRIPING-TEMP PAINT-4 IN	26,000.00	LF		\$	
190	06514		PAVE STRIPING-PERM PAINT-4 IN	34,000.00	LF		\$	
200	24381EC		G/R STEEL W BEAM-S FACE (NESTED)	62.50	LF		\$	

Section: 0002 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0210	00001		DGA BASE	40.00	TON		\$	
0220	02483		CHANNEL LINING CLASS II	50.00	TON		\$	
0230	20257NC		SITE PREPARATION (BRIDGE)	1.00	LS		\$	
0240	21415ND		EROSION CONTROL (BRIDGE)	1.00	LS		\$	
0250	23060EN		PRECAST CONCRETE ARCH CULVERT	28.00	LF		\$	

Section: 0003 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP AMOUNT
0260	02569		DEMOBILIZATION	1.00	LS		\$